

**DRAFT**

---

**RCRA CLOSURE REPORT**  
**BUILDING 307, HAZARDOUS WASTE CONTAINER STORAGE FACILITY**  
**BUILDING 301, TRANSFORMER STORAGE BUILDING**

---

*Prepared For:*

**Seneca Army Depot Activity**

Route 96  
Romulus, NY

**U.S. Army Corps of Engineers**

Huntsville Engineering and Support Center

and

**U.S. Army Corps of Engineers**

New York District

*Prepared By:*

**PARSONS**

290 Elwood Davis Road, Suite 312  
Liverpool, New York 13088  
Phone: (315) 451-9560  
Fax: (315) 451-9570

**REVIEWED AND APPROVED BY:**

Project Manager:

9-4-03

Date

Technical Manager:

9-4-03

Date

**SEPTEMBER 2003**

# TABLE OF CONTENTS

<b>LIST OF ACRONYMS.....</b>	<b>v</b>
<b>PROFESSIONAL ENGINEER CERTIFICATION.....</b>	<b>VI</b>
<b>SECTION 1 INTRODUCTION.....</b>	<b>1-1</b>
1.1 Summary .....	1-1
1.2 Site Description.....	1-1
1.2.1 Building 307 – Hazardous Waste Container Storage Facility (SEAD-1)	1-2
1.2.2 Building 301 – Transformer Storage Building (SEAD-2).....	1-2
1.3 Closure Performance Standard.....	1-3
1.4 Conclusions.....	1-3
<b>SECTION 2 CLOSURE ACTIVITIES.....</b>	<b>2-1</b>
2.1 Removal of Hazardous Waste Inventory .....	2-1
2.1.1 Building 307 .....	2-1
2.1.2 Building 301 .....	2-1
2.2 Decontamination .....	2-1
2.2.1 Building 307 .....	2-1
2.2.2 Building 301 .....	2-1
2.3 Confirmatory Sampling.....	2-1
2.3.1 Rinsate Samples .....	2-2
2.3.2 PCB Wipe Samples.....	2-2
2.3.3 PCB Chip Samples.....	2-3
2.3.4 Building 307 Confirmation Samples .....	2-3
2.3.5 Building 301 Confirmation Samples .....	2-3
2.4 Disposal.....	2-4
2.4.1 Decontamination Water .....	2-4
2.4.2 Personal Protective Equipment.....	2-4
2.5 Data Reporting .....	2-4
2.5.1 Building 307 .....	2-4
2.5.1.1 Rinsate Samples .....	2-4
2.5.1.2 PCB Wipe Samples.....	2-5
2.5.2 Building 301 .....	2-5

2.5.2.1 Rinsate Samples.....	2-5
2.5.2.2 PCB Wipe Samples.....	2-5
2.5.2.3 PCB Chip Samples.....	2-5
2.6 Grounds Surrounding Buildings .....	2-6
2.6.1 Building 307 .....	2-6
2.6.1.1 Soil Sample Results .....	2-6
2.6.2 Building 301 .....	2-6
2.6.2.1 Soil Sample Results .....	2-6
2.7 Survey Plat .....	2-7
2.8 Professional Engineer Review and Certificatification .....	2-7
2.9 Schedule .....	2-7
2.10 Photographic Documentation.....	2-7
<b>SECTION 3 DATA ANALYSIS .....</b>	<b>3-1</b>
3.1 Building 307.....	3-1
3.1.1 Rinsate Samples.....	3-1
3.1.2 PCB Samples .....	3-1
3.1.3 Soil Samples .....	3-1
3.2 Building 301.....	3-2
3.2.1 Rinsate Samples.....	3-2
3.2.2 PCB Samples .....	3-2
3.2.3 Soil Samples .....	3-2
3.3 Conclusions.....	3-3
3.3.1 Building 307 .....	3-3
3.3.2 Building 301 .....	3-3
3.4 Recommendations.....	3-4

**APPENDIX A ANALYTICAL RESULTS**

**APPENDIX B DISPOSAL DOCUMENTATION**

**APPENDIX C DAILY FIELD REPORTS**

## LIST OF FIGURES

Figure 1-1 Site Location Plan.....	1-4
Figure 2-1 Building 307 Rinsate Sample Locations .....	2-12
Figure 2-2 Building 307 PCB Wipe Sample Locations .....	2-13
Figure 2-3 Building 301 Rinsate Sample Locations .....	2-14
Figure 2-4 Building 301 PCB Sample Locations.....	2-15
Figure 2-5 Building 307 Soil Sample Locations.....	2-16
Figure 2-6 Building 301 Soil Sample Locations.....	2-17

## LIST OF TABLES

Table 2-1 SEAD-1 (Building 307) Rinsate Sample Data Exceedance Compounds Only.....	2-8
Table 2-2 SEAD-2 (Building 301) Rinsate Sample Data Exceedance Compounds Only.....	2-9
Table 2-3 SEAD-1 (Building 307) Exterior Soil Data Exceedance Compounds Only.....	2-10
Table 2-4 SEAD-2 (Building 301) Exterior Soil Data Exceedance Compounds Only.....	2-11

## LIST OF ACRONYMS

CFR	Code of Federal Regulations
EPA	Environmental Protection Agency
GEL	Groundwater Effluent Limitation
NYCRR	New York Code of Rules and Regulations
NYS	New York State
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
NYSWQS	New York State Water Quality Standard
PCB	Polychlorinated Biphenyls
ppb	parts per billion
ppm	parts per million
QA/QC	Quality Assurance/Quality Control
RCRA	Resource Conservation and Recovery Act
SEDA	Seneca Army Depot Activity
Standard	New York State Water Quality Standard
TAGM	Technical and Administrative Guidance Memorandum
TAL	Target Analyte List
TSCA	Toxic Substance Control Act
TCL	Target Compound List
ug/kg	micrograms per kilogram (ppb)
US	United States

## PROFESSIONAL ENGINEER CERTIFICATION

To the best of my knowledge, after thorough investigation, I certify that the information contained in or accompanying this submission is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

---

David B. Babcock, P.E.  
Parsons  
NYS Professional Engineer 065209-1

# SECTION 1

## INTRODUCTION

This Closure Report details the work completed as proposed in the Resource Conservation and Recovery Act (RCRA) Closure Plan (Parsons, December 2002) and approved by the New York State Department of Environmental Conservation (NYSDEC) (letter dated March 31, 2003). Parsons was retained by the United States (US) Army to perform RCRA closure of two Hazardous Waste Management Units (Building 307 and Building 301) at Seneca Army Depot in Romulus, New York. The objective of the work was to obtain regulatory closure by meeting the objectives of Title 6 New York Code of Rules and Regulations (6 NYCRR) Subpart 373-3.7, Interim Status Standards for Owners and Operators of Hazardous Waste Facilities (New York State Department of Environmental Conservation (NYSDEC), March 15, 2002).

### 1.1 SUMMARY

Building 307 and Building 301 were decontaminated by high pressure washing with detergent and triple rinsing with clean water obtained from on-site fire hydrants. The buildings were sampled for Volatile Organic Compounds (VOC), Semi-Volatile Organic Compounds (SVOC), Polychlorinated Biphenyls (PCB) and heavy metals.

In addition, the grounds adjacent to the buildings were investigated, by sampling, for the presence of hazardous materials that may have been associated with the use of these buildings. Soils were analyzed for VOC, SVOC, PCB and heavy metals.

The RCRA closure work was performed in strict accordance with the approved RCRA closure plan and in accordance with 6 NYCRR Subpart 373-3.7, Interim Status Standards for Owners and Operators of Hazardous Waste Facilities (NYSDEC, March 15, 2002).

This report documents all closure activities associated with Building 307 (the former Hazardous Waste Container Storage Facility) and Building 301 (the former Transformer Storage Building). Included are analytical results (Appendix A), disposal documentation (Appendix B) and Daily Field Reports (Appendix C).

### 1.2 SITE DESCRIPTION

Building 307 and Building 301 are located within the Seneca Army Depot Activity (SEDA), a 10,587 acre facility located in Seneca County, near the village of Romulus, New York (Figure 1). The facility has been owned by the United States Government and operated by the Department of the Army since 1941. Since its inception in 1941, SEDA's primary mission was the receipt, storage, maintenance and supply of military items.

### **1.2.1 Building 307 – Hazardous Waste Container Storage Facility (SEAD-1)**

Building 307 is located in the eastern portion of SEDA, approximately 3,500 feet southwest of the Depot's main entry gate off New York State Route 96. The Army constructed Building 307 in 1981. Building 307 was used for storage of hazardous waste generated throughout the Depot prior to their shipment offsite for disposal. Hazardous wastes stored within Building 307 included spent solvents, still bottoms from 1,1,1-trichloroethene vapor degreasers, sludge from oil/grease separations, cleaning compounds, paper filters from paint spray booths, and spent battery acids. Most wastes stored within the building were stored in new 55-gallon drums, but occasionally small amounts of hazardous waste were stored in 5-gallon pails.

Building 307 measures 40-feet wide by 50-feet long and its sides and roof are corrugated metal construction. The corrugated metal structure sits on a six-inch thick monolithic, reinforced concrete slab floor that is surrounded by an integral component, six-inch concrete curb. The floor of the building is sealed to prevent seepage in the event that materials were spilled onto the concrete floor. Other than the portion of the floor that is covered by the access/egress ramp, the monolithic floor of the building is not sloped nor does it contain any collection sumps or drains. The only entrance into the building is through a sliding corrugated-steel door located on the south side of the building. A 10-foot wide concrete access/egress ramp extends 10 feet beyond the exterior of the building and 8 feet into the building's interior.

### **1.2.2 Building 301 – Transformer Storage Building (SEAD-2)**

Building 301 is located in the east central portion of SEDA, approximately 6,000 feet west, southwest of the Depot's main entry gate off New York State Route 96. The building is located near the munitions igloo storage area. The Army constructed Building 301 in 1942. The building was upgraded in 1986 to meet hazardous waste storage requirements. The Army has used Building 301 as a PCB Storage Facility since approximately 1980. Building 301 was used for the storage of materials associated with unserviceable transformers or other electrical equipment that were known, or suspected, to contain PCBs.

The exterior dimensions of Building 301 are 35 feet 4 inches long by 23 feet 4 inches wide, and the main structure is bounded partially on two sides (east and west), and completely on a third side (i.e., north) by a raised loading dock or platform that measures 6 feet 4 inches in width. The raised loading platform ramps to ground surface on the western side of the building, and a stairway provides transition from the ground to the raised loading dock halfway along the eastern side of the building.

A gravel and tar roof sits on pre-cast concrete planks supported by steel trusses. The exterior walls are 12-foot high and made of 12-inch thick tile. Access to the building from the loading dock is provided through either of two 8-foot by 8-foot overhead doors; one access door is located on the northern side of the building while the second is located on the eastern side of the building.

Routine inspections indicate that there is no evidence of historic release within the building and that the building is in good structural condition. As part of the 1986 Building 301 Upgrade Program, four surface soil samples were collected from each of the exterior corners of the



building and analyzed to determine total PCB content. The results of this sampling show that each of the four samples contained less than 1 part per million (ppm) of total PCBs.

### 1.3 CLOSURE PERFORMANCE STANDARD

The closure performance standard as written in 6 NYCRR Part 373-3.7(b) states that the facility must be closed in a manner that:


- Minimizes the need for further maintenance;
- Controls, minimizes or eliminates, to the extent necessary to protect human health and the environment, post closure escape of hazardous waste, hazardous constituents, leachate, contaminated run-off, or hazardous waste decomposition products to the ground or surface waters or to the atmosphere;

Subdivisions of 373 3.10(h), 3.11(f), 3.12(g), 3.13(g), 3.14(d), 3.15(e), 3.16(e), 3.17(e) and 3.30(c) are NOT applicable to this closure, as written in the standard.


### 1.4 CONCLUSIONS

The primary objective of this work was to perform the work necessary to obtain clean closure of the buildings in conformance with the closure performance standard. Review of the confirmatory rinsate analytical data indicates only minor exceedances of the New York State Standards that were used to assess the level of decontamination achieved. The rinsate analytical results indicate the levels of the exceedance compounds were far below hazardous waste concentrations. In fact, the wash water was disposed of as a non-hazardous/non-regulated waste. Therefore, it can be concluded that;

- No further maintenance is needed;
- The buildings pose no threat to human health or the environment;
- Because all hazardous materials have been removed and the buildings decontaminated, there is no chance for post closure escape of hazardous waste or hazardous constituents.
- Because the buildings are in good repair and are no longer used for storage of hazardous materials, there is no chance for future leachate, contained run-off or hazardous waste decomposition products migrating to the ground, surface waters or to the atmosphere.
- Soils surrounding the buildings do not appear to be impacted by the former use of the buildings. The analytical results for the soils indicate the presence of SVOC and metals in concentrations typical of an industrial setting.



REGIONAL MAP  
SCALE: 1 INCH=2.5 MILES  
SOURCE: Mopquest.com



SITE MAP  
SCALE: 1 INCH=10,000 FEET

**FIGURE 1-1**

SENECA ARMY DEPOT ACTIVITY  
RCRA HAZARDOUS WASTE STORAGE FACILITY  
TRANSFORMER STORAGE BUILDING

**SITE LOCATION PLAN**

**PARSONS**  
290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9560

## **SECTION 2**

### **CLOSURE ACTIVITIES**

#### **2.1 REMOVAL OF HAZARDOUS WASTE INVENTORY**

All hazardous waste inventory was removed prior to the start of this closure work.

##### **2.1.1 Building 307**

No hazardous waste was removed during this closure activity. The last shipment of hazardous waste was removed from Building 307 in March 2002.

##### **2.1.2 Building 301**

No hazardous waste was removed during this closure activity. The last shipment of PCB containing waste was removed from Building 301 in 1998.

#### **2.2 DECONTAMINATION**

The buildings were decontaminated manually to the extent practical through the use of rigorous industrial cleaning methods.

##### **2.2.1 Building 307**

All interior floor and wall surfaces were decontaminated using a high-pressure detergent and water wash, followed by three clear water rinses using a high-pressure hose. During each of the wash and rinse cycles, the doorway was sealed to prevent the spread of wash and rinse waters beyond the inside of the building and the containment area.

##### **2.2.2 Building 301**

All interior floor and wall surfaces were decontaminated using a high-pressure detergent and water wash, followed by three clear water rinses using a high-pressure hose. During each of the wash and rinse cycles, the doorways were sealed to prevent the spread of wash and rinse waters beyond the inside of the building and the containment area.

Exterior floor surfaces were decontaminated using a high-pressure detergent and water wash, followed by three clear water rinses using a high-pressure hose. Temporary containment, consisting of polyethylene sheeting, was used to prevent the spread of wash and rinse waters beyond the intended containment area.

#### **2.3 CONFIRMATORY SAMPLING**

After completion of the decontamination process, samples were collected to confirm the degree of decontamination achieved. Confirmation sampling included the collection of aqueous samples in accordance with the State of New York's "Rinsate Sample Collection Protocol" and

**PARSONS**

the collection of wipe samples in accordance with procedures that are specified under the Toxic Substance Control Act (TSCA) regulations [40 Code of Federal Regulations (CFR) § 761.123].

### **2.3.1 Rinsate Samples**

Rinsate samples were collected from areas that were generally flat and horizontal (i.e. floors and ramps) where damming techniques could be successfully implemented. Prior to collecting rinsate samples, grids were laid out on the floors of the buildings by placing chalk marks at the appropriate intervals, and sampling locations were chosen based on a random numbering selection process.

An Ultra Spill Berm® (temporary floor dike made of a flexible, non absorbing polyurethane) was used to contain rinsate water. The berm was shaped into an approximately 400 square inch surface area (i.e., 20 inches by 20 inches). Sampling was initiated by pouring approximately 2 liters of laboratory grade water into the bermed area and letting it stand for ten minutes.

The water was sampled from the bermed area using a peristaltic pump with dedicated tubing. Each sample was labeled and recorded (Sample ID, Location ID, and time) in the field logbook and on the chain of custody.

After each sample, the berm was decontaminated using alconox and water followed by a laboratory grade water rinse. The dedicated tubing was disposed after use.

Rinsate samples were analyzed for Target Compound List (TCL) VOC, SVOC, and Target Analyte List (TAL) metals. All sample analyses were conducted by General Engineering Laboratories, LLC, a laboratory certified by the New York State Department of Health (NYSDOH), and were performed in accordance with "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods," EPA Publication SW-846 (Third Edition (November 1986), as amended by Updates: I (July 1992), II (September 1994), IIA (August 1993), IIB (January 1995), III (December 1996), and IIIA (April 1998), and later approved revisions), hereinafter referred to as "SW-846".

### **2.3.2 PCB Wipe Samples**

PCB wipe samples were collected from the horizontal and vertical non-porous surfaces in the buildings. A sampling grid was developed for the buildings in accordance with the EPA's guidance manual "Field Manual for Grid Sampling of PCB Spill Sites to Verify Clean-up" (EPA-560/5-86-017). Each sampling location was marked out with tape and labeled.

In order to conform to TSCA's recommended 100 square centimeter surface area, 10 centimeter square templates were utilized.

The wipe samples were collected by placing the template over the area to be sampled, grasping the wipe with forceps, and wiping in a left to right motion and then top to bottom motion. The wipe was air-dried, folded over, and placed in the container. Each sample was labeled and recorded (Sample ID, Location ID, and time) in the field logbook and on the chain of

custody. The forceps were decontaminated using alconox and water followed by a hexane rinse. The forceps were allowed to air dry.

Wipe samples were analyzed for PCBs. All sample analyses were conducted by General Engineering Laboratories, LLC, a laboratory that is certified by the NYSDOH, and were performed in accordance with "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods," EPA Publication SW-846, Appendix 19 of 6NYCRR Part 371.

### **2.3.3 PCB Chip Samples**

Chip samples were collected in lieu of wipe samples where surfaces were tar and gravel coatings (i.e., exterior floor slabs and ramps). All sample analyses were conducted by General Engineering Laboratories, LLC, a laboratory that is certified by the NYSDOH, and were performed in accordance with "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods," EPA Publication SW-846.

Chip samples were collected from the tar/gravel ramp locations on the exterior of Building 301. The samples were collected by placing a 10 centimeter square template on the surface and chipping the surface, no more than 1 cm deep, and collecting approximately 50 grams of the surface material.

### **2.3.4 Building 307 Confirmation Samples**

Seventeen (17) locations were chosen for collection of rinsate samples, plus additional quality assurance and quality control (QA/QC) samples. The samples were collected from the surfaces (i.e., ramps and contained floor) of Building 307. Three samples (15, 64, 77) were collected from areas that were visibly stained. See Figure 2-1 for locations.

Forty (40) wipe samples, plus additional QA/QC samples were collected from locations on the interior walls and floor of Building 307. See Figure 2-2 for locations.

### **2.3.5 Building 301 Confirmation Samples**

Fifteen (15) locations were chosen for collection of rinsate samples, plus additional QA/QC samples. The samples were collected from the surfaces (i.e., ramps and contained floor) of Building 301. See Figure 2-3 for locations.

The exterior ramp and loading dock surface finish is made of gravel and tar/asphalt aggregate. Samples from these areas are 1, 4, 13, 30, 90 and 93.

Sample #84 was collected on the stairs adjacent to the railroad tracks.

Sixteen (16) wipe samples, plus additional QA/QC samples were collected from locations on the interior walls and floor of Building 307. See Figure 2-4 for locations.

Six (6) chip samples and one (1) duplicate sample were collected from locations on the exterior surfaces of Building 301. See Figure 2-4 for locations.

## 2.4 DISPOSAL

### 2.4.1 Decontamination Water

Wastewater generated during the wash and rinse cycles was collected and pumped into DOT-approved 55-gallon drums. Eight drums of washwater were collected (three from Building 301 and five from Building 307). A sample of the drummed waters was collected and analyzed for TCL VOC, SVOC, PCB and TAL metals. Based on the analytical results, the water was determined to be a non-hazardous waste. A waste profile was generated and the water was shipped to Industrial Oil Services Corp. in Oriskany, NY for disposal. See Appendix A for analytical results and Appendix B for disposal documentation.

All pumps, hoses, containers and equipment used during the decontamination operations were decontaminated after use by triple flushing/rinsing all exposed or wetted surfaces. The rinse waters were added to the drummed decontamination liquid drums and disposed.

### 2.4.2 Personal Protective Equipment

Disposable personnel protective equipment worn by workers was collected and placed in two 55-gallon drums for disposal as a non-hazardous waste at Industrial Oil Services Corp. in Oriskany, NY. See Appendix B for disposal documentation.

## 2.5 DATA REPORTING

### 2.5.1 Building 307

#### 2.5.1.1 Rinsate Samples

Analytical results from rinsate samples are listed on Table A-1 (Appendix A) and compared to New York State Water Quality Standards-Class GA (NYSWQS) (6 NYCRR § 703.5). Seven (7) compounds were detected at concentrations exceeding the NYSWQS (Table 2-1).

Toluene was detected in 4 of 18 samples. Toluene exceeded the NYSWQS (Standard) of 5 ug/L in 3 of 18 samples with a maximum value of 17.2 ug/L.

Bis(2-Ethylhexyl)phthalate was detected in 6 of 18 samples. Bis(2-Ethylhexyl)phthalate exceeded the Standard of 5 ug/L in 5 of 18 samples with a maximum value of 10.8 ug/L.

Pentachlorophenol was detected in 2 of 18 samples. Pentachlorophenol exceeded the Standard of 1 ug/L in 2 of 18 samples with a maximum value of 8.9 ug/L.

Arsenic was detected in 15 of 19 samples. Arsenic exceeded the Standard of 25 ug/L in five of 18 samples with a maximum value of 30.1 ug/L. No arsenic concentrations were greater than the NYS Groundwater Effluent Limitation-Class GA (GEL) of 50 ug/L.

Cadmium was detected in 17 of 19 samples. Cadmium exceeded the Standard of 5 ug/L in 2 of 18 samples with a maximum value of 7.18 ug/L. No cadmium concentrations were greater than the GEL of 10 ug/L.

---

**PARSONS**

Iron was detected in 17 of 19 samples. Iron exceeded the Standard of 300 ug/L in 16 of 18 samples with a maximum value of 3,880 ug/L.

Lead was detected in 18 of 19 samples. Lead exceeded the Standard of 25 ug/L in 13 of 19 samples with a maximum value of 165 ug/L.

### **2.5.1.2 PCB Wipe Samples**

Analytical results from the PCB wipe samples are listed on Table A-2 (Appendix A) and compared to the 10 ug/100 cm<sup>2</sup> decontamination standard for non-porous surfaces (40 CFR 761.125). There were no detections or exceedances of the 10 ug/ 100 cm<sup>2</sup> decontamination standard.

## **2.5.2 Building 301**

### **2.5.2.1 Rinsate Samples**

Analytical results from rinsate samples are listed on Table A-3 (Appendix A) and compared to New York State Water Quality Standards for Class GA groundwater (6 NYCRR § 703.5). Six compounds were detected at concentrations exceeding the NYSWQS (Table 2-2).

1,1'-Biphenyl was detected in 3 of 13 samples. 1,1'-Biphenyl exceeded the Standard of 5 ug/L in 1 of 13 samples with a maximum value of 7.7 ug/L.

3 or 4-Methylphenol was detected in 1 of 13 samples. 3 or 4-Methylphenol exceeded the Standard of 1 ug/L in 1 of 13 samples with a maximum value of 7.7 ug/L.

Bis(2-Ethylhexyl)phthalate was detected in 6 of 13 samples. Bis(2-Ethylhexyl)phthalate exceeded the Standard of 5 ug/L in 2 of 13 samples with a maximum value of 12.7 ug/L.

Cadmium was detected in 4 of 16 samples. Cadmium exceeded the Standard of 5 ug/L in 1 of 16 samples with a maximum value of 6.23 ug/L. No cadmium concentrations were greater than the GEL of 10 ug/L.

Iron was detected in 16 of 16 samples. Iron exceeded the Standard of 300 ug/L in 6 of 16 samples with a maximum value of 2,930 ug/L.

Lead was detected in 16 of 16 samples. Lead exceeded the Standard of 25 ug/L in 12 of 16 samples with a maximum value of 1,050 ug/L.

### **2.5.2.2 PCB Wipe Samples**

Analytical results from the PCB wipe samples are listed on Table A-4 (Appendix A) and compared to the 10 ug/100 cm<sup>2</sup> decontamination standard for non-porous surfaces. There were no detections or exceedances of the 10 ug/ 100 cm<sup>2</sup> decontamination standard.

### **2.5.2.3 PCB Chip Samples**

Analytical results from the chip samples are listed on Table A-5 (Appendix A) and compared to the 1,000 ug/kg standard for surface soils (New York State Technical and

Administrative Guidance Memorandum (TAGM) 4046; Appendix A; Table 3). No exceedances of the 1,000 ug/kg were observed.

## **2.6 GROUNDS SURROUNDING BUILDINGS**

No records of historical spills or releases of chemical materials exterior to Buildings 301 or 307 exist. Soil samples were collected to determine if evidence of a possible hazardous material release exists in the shallow soils surrounding the buildings. The samples were collected using a stainless steel spoon and mixing bowl from the top two to three inches of soil. VOC samples were collected in a 5-gram syringe and placed in VOA vials. The soil samples were analyzed for TCL VOC, SVOC, PCB, and TAL metals.

### **2.6.1 Building 307**

Twelve (12) shallow surface soil samples, plus additional QA/QC samples, were collected from the soil exterior of Building 307. See Figure 2-5 for locations.

The surface surrounding Building 307 consisted of coarse gravel and vegetation. As necessary, this surface cover was removed and the native soils were sampled. All samples were collected within two feet of the exterior walls.

#### **2.6.1.1 Soil Sample Results**

Analytical results from the soil samples are listed on Table A-6 (Appendix A). Six compounds were detected at concentrations exceeding the TAGM 4046 Soil Cleanup Objectives (Table 2-3).

### **2.6.2 Building 301**

Twelve (12) shallow surface soil samples, plus additional QA/QC samples were collected from the soil exterior of Building 301. See Figure 2-6 for locations.

The surface surrounding Building 301 was comprised of a tar/asphalt and gravel material on the north, east and west sides (all samples, except 04). The south side surface was grassy. On the east side, the surface soil samples were collected within 7 feet of the railroad tracks (05, 06) and sample location 07 and 08 were 3 feet and 1.5 feet from the railroad tracks, respectively. Additionally, all samples were collected from within 2 feet of the Building 301 wall, with the exception of sample 04, which was approximately 8 feet from the wall. Sample 04 was moved 8 feet from the wall to avoid a concrete pad so that native soils could be sampled.

The field crew removed the top cover of asphalt/tar and attempted to only sample the underling soil. Attempts were made to remove any asphalt/tar material before collecting the sample.

#### **2.6.2.1 Soil Sample Results**

Analytical results from the soil samples are listed on Table A-7 (Appendix A). Nineteen compounds were detected at concentrations exceeding the TAGM 4046 Soil Cleanup Objectives (Table 2-4).

---

**PARSONS**



## **2.7 SURVEY PLAT**

Not required. No hazardous wastes are remaining at these sites.

## **2.8 PROFESSIONAL ENGINEER REVIEW AND CERTIFICATION**

As per 6 NYCRR Part 373-3.7(f), this report shall serve as certification of the closures of Building 307 and Building 301. David Babcock, P.E. has reviewed this report and certifies that the work was done in accordance with the approved closure plan and 6 NYCRR Part 373-3.7. See Certification of Closure at the beginning of this report.

## **2.9 SCHEDULE**

A letter announcing the intended closure work schedule was forwarded to the NYSDEC on April 4, 2003.

Building decontamination was completed between April 14, 2003 and April 16, 2003.

Post decontamination confirmatory sampling started on April 17, 2003 and was completed on April 24, 2003.

## **2.10 PHOTOGRAPHIC DOCUMENTATION**

Photographic documentation of the decontamination effort and the confirmatory sampling can be found in the Daily Field Reports in Appendix C.

SEAD-1 (BUILDING 307)  
RINSATE SAMPLE DATA  
EXCEEDANCE COMPOUNDS ONLY

Location ID							INT/FLR	INT/FLR	INT/FLR	INT/FLR	INT/FLR	INT/FLR	INT/FLR	INT/FLR
Bldg ID/Grid Number (2)							R307-4	R307-13	R307-13	R307-15	R307-16	R307-18	R307-64	R307-77
Sample Type							RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE
Field Sample ID							15001	15004	15003	15013	15002	15000	15011	15012
Sample Date							4/22/2003	4/22/2003	4/22/2003	4/23/2003	4/22/2003	4/22/2003	4/23/2003	4/23/2003
Sample Designation							SA	DU	SA	SA	SA	SA	SA	SA
Parameter	Units	Maximum Detected Value	Action Level	No. of Exceedances	No. of Detections	No. of Samples Analyzed (1)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Toluene	UG/L	8.4	5	3	4	18	8.4	1 U	1 U	1 U	1 U	6.7	1 U	1 U
Bis(2-Ethylhexyl)phthalate	UG/L	10.8	5	5	6	18	10.3 U	10.2 U	10.2 U	11.1 U	10.3 U	12.2 U	5.6 J	7.1 J
Pentachlorophenol	UG/L	8.9	1	2	2	18	10.3 U	10.2 U	10.2 U	11.1 U	10.3 U	8.9 NJ	11 U	9.7 R
Arsenic	UG/L	30.1	25	5	15	19	9.59	27.3	14.1	7.26	10.8	26.4	16.9	4.1 U
Cadmium	UG/L	7.18	5	2	17	19	1.27 J	4.16	2.05	0.808 J	1.57	7.18	5.76	0.807 U
Iron	UG/L	3880	300	14	17	19	843	3830	1740	653	1640	3190	3880	82
Lead	UG/L	165	25	13	18	19	73.1	165	88.2	27.4	42.7	116	118	10.1

Location ID							INT/FLR	INT/FLR	INT/FLR	INT/RAMP	INT/RAMP	EXT/RAMP	INT/FLR
Bldg ID/Grid Number (2)							R307-84	R307-90	R307-90	R307-RMP-1 (49)	R307-RMP-2 (58)	R307-EXT	R307-EXT2
Sample Type							RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE
Field Sample ID							15009	15010	015010D	15014	15015	15016	15017
Sample Date							4/22/2003	4/22/2003	4/22/2003	4/23/2003	4/23/2003	4/23/2003	4/23/2003
Sample Designation							SA	SA	DU	SA	SA	SA	SA
Parameter	Units	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	
Toluene	UG/L	1 U	1 U			1 U	1 U	1 U	1 U	1 U	17.2		
Bis(2-Ethylhexyl)phthalate	UG/L	10.2 U	4.6 U			8.7 J	5.9 J	10.8 J	3.6 J				
Pentachlorophenol	UG/L	10.2 U	5.9 J			10.5 U	9.6 U	11.2 U	9.9 U				
Arsenic	UG/L	26.3	30.1	29.4		5.02	8.75	4.1 U	4.1 U				
Cadmium	UG/L	2.03	3.25	3.39		1.3 J	2.79 J	0.877 J	0.807 U				
Iron	UG/L	1890	767	736		2390	1760	2450	1270				
Lead	UG/L	64.9	125	124		81.6	115	106	16.9				

NOTES:

- SA = Sample
- DU = Duplicate
- Q = Data Qualifier
- U = Undetected
- J = Estimated
- R = Rejected
- FLR = Floor (Coated Concrete)
- INT = Interior
- EXT = Exterior
- RAMP = RAMP Entrance to Building
- RMP = Ramp

NOTES:

- (1) - Number of samples analyzed includes all QA/QC samples  
Samples with no exceedances do not appear on this table
- (2) - The 2nd part of the designation identifies the grid location on Figure 2-1  
(i.e: R307-4 = grid #4)

SEAD-2 (BUILDING 301)  
RINSATE SAMPLE DATA  
EXCEEDANCE COMPOUNDS ONLY

Location ID							EXT/DOCK	EXT/DOCK	EXT/DOCK	EXT/DOCK	EXT/RAMP	EXT/RAMP	EXT/STAIR
Bldg ID/Grid Number (2)							R301-1	R301-4	R301-13	R301-90	R301-30	R301-93	R301-84
Sample Type							RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE
Field Sample ID							25011	25015	25014	25010	25013	25012	25009
Sample Date							4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003
Sample Designation							SA	SA	SA	SA	SA	SA	SA
Parameter	Units	Maximum Detected Value	Action Level	No. of Exceedances	No. of Detections	No. of Samples Analyzed (1)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
1,1'-Biphenyl	UG/L	7.7	5	1	3	13	44.4 U	0.51 J	2.2 J	7.7 J	10.9 U		
3 or 4-Methylphenol	UG/L	3.4	1	1	1	13	44.4 U	9.9 U	40 U	3.4 J	10.9 U		
Bis(2-Ethylhexyl)phthalate	UG/L	12.7	5	2	6	13	6.8 U	4.2 U	40 U	40.8 U	5.4 U		
Cadmium	UG/L	6.23	5	1	4	16	0.807 U	0.807 U	0.807 U	4.17	0.807 U	0.807 U	6.23
Iron	UG/L	2930	300	6	16	16	302	2050	639	2320	296	168	2930
Lead	UG/L	1050	25	12	16	16	93.2	284	64	1090	112	213	602

Location ID							INT/FLR	INT/RAMP	INT/FLR	INT/FLR	INT/FLR	INT/RAMP
Bldg ID/Grid Number (2)							R301-28	R301-42	R301-43	R301-63	R301-65	R301-73
Sample Type							RINSATE	RINSATE	RINSATE	RINSATE	RINSATE	RINSATE
Field Sample ID							25000	25008	25007	25006	25004	25005
Sample Date							4/23/2003	4/23/2003	4/23/2003	4/23/2003	4/23/2003	4/23/2003
Sample Designation							SA	SA	SA	SA	SA	SA
Parameter	Units	Maximum Detected Value	Action Level	No. of Exceedances	No. of Detections	No. of Samples Analyzed (1)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
1,1'-Biphenyl	UG/L						10.8 U	11.1 U	10 U	10.8 U	11.1 U	
3 or 4-Methylphenol	UG/L						10.8 U	11.1 U	10 U	10.8 U	11.1 U	
Bis(2-Ethylhexyl)phthalate	UG/L						3.3 J	4.4 J	12.7	9.5 J	2.1 J	
Cadmium	UG/L						0.807 U	1.2 J	0.807 U	0.807 U	0.807 U	1.57 B
Iron	UG/L						466	76.5	102	20.7 J	26.7 J	205
Lead	UG/L						584	146	209	22	78.7	304

NOTES:

- SA = Sample
- DU = Duplicate
- Q = Data Qualifier
- U = Undetected
- J = Estimated
- B =
- DOCK = Loading Dock (Gravel on Tar/Asphalt Base over Concrete)
- EXT = Exterior
- INT = Interior
- RAMP = Ramp Entrance to Building
- FLR = Floor (Coated Concrete)
- STAIR = Concrete Stairs

NOTES:

- (1) - Number of samples analyzed includes all QA/QC samples  
Samples with no exceedances do not appear on this table
- (2) - The 2nd part of the designation identifies the grid location on Figure 2-3  
(i.e: R301-1 = grid #1)

SEAD-1 (BLDG 307)  
EXTERIOR SOIL DATA  
EXCEEDANCE COMPOUNDS ONLY

Location ID							SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1
Bldg ID/Sample Location (2)							SS307-00	SS307-11	SS307-01	SS307-02	SS307-03	SS307-04	SS307-05
Sample Type							SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Field Sample ID							11000	11011	11001	11002	11003	11004	011005D
Sample Date							4/18/2003	4/18/2003	4/18/2003	4/18/2003	4/18/2003	4/18/2003	4/18/2003
Sample Designation							SA	DU	SA	SA	SA	SA	DU
Parameter	Units	Maximum Detected Value	Action Level	No. of Exceedances	No. of Detections	No. of Samples Analyzed (1)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Benzo(a)anthracene	UG/KG	514	224	3	7	12	140 U	145 U	402	514	202	34.9 U	
Benzo(a)pyrene	UG/KG	561	61	11	11	12	140 UJ	334 NJ	387	561	283	105	
Benzo(b)fluoranthene	UG/KG	1140	1100	1	12	12	692 J	840	866	1140	344	237	
Chrysene	UG/KG	591	400	3	12	12	383	427	405	591	239	118	
Calcium	UG/KG	306000000	293000000	1	13	13	209000000	155000000	178000000	245000000	173000000	196000000	127000000
Mercury	UG/KG	370	130	2	13	13	65.1	61.8	36.9	18.8	22.1	39.8	370
Sodium	UG/KG	348000	269000	1	12	13	88100	68000	77700	348000	85200 U	232000	51200
Zinc	UG/KG	16200000	126000	13	13	13	2930000	2470000	905000	16200000	9650000	5800000	180000

Location ID							SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1
Bldg ID/Sample Location (2)							SS307-05	SS307-06	SS307-07	SS307-08	SS307-09	SS307-10
Sample Type							SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Field Sample ID							11005	11006	11007	11008	11009	11010
Sample Date							4/18/2003	4/18/2003	4/18/2003	4/18/2003	4/18/2003	4/18/2003
Sample Designation							SA	SA	SA	SA	SA	SA
Parameter	Units	Maximum Detected Value	Action Level	No. of Exceedances	No. of Detections	No. of Samples Analyzed (1)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Benzo(a)anthracene	UG/KG						211	38.4 U	185	291	36.7 U	166
Benzo(a)pyrene	UG/KG						283	188	273	360	162	226
Benzo(b)fluoranthene	UG/KG						367	387	383	578	245	308
Chrysene	UG/KG						188	194	219	302	190	159
Calcium	UG/KG						109000000	134000000	409000000	727000000	306000000	159000000
Mercury	UG/KG						354	47.3	48.3	62	13.9	64.1
Sodium	UG/KG						46200	177000	161000	158000	88600	96700
Zinc	UG/KG						157000	6350000	8660000	14100000	3020000	1050000

NOTES:

- SA = Sample
- DU = Duplicata
- SS = Surface Soil
- Q = Data Qualifier
- U = Undetected
- J = Estimated

NOTES:

- (1) - Number of samples analyzed includes all QA/QC samples
- (2) - The 2nd part of the designation identifies the sample location on Figure 2-5 (i.e: SS307-00 = sample #00)

SEAD-2 (BLDG 301)  
EXTERIOR SOIL DATA  
EXCEEDANCE COMPOUNDS ONLY


Location ID	SEAD-2		SEAD-2		SEAD-2		SEAD-2		SEAD-2		SEAD-2		SEAD-2		SEAD-2		SEAD-2		SEAD-2							
Bldg ID/Location (2)	SS301-00		SS301-01		SS301-02		SS301-03		SS301-04		SS301-04		SS301-05		SS301-08		SS301-07		SS301-08		SS301-09		SS301-20		SS301-21	
Sample Type	SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL	
Field Sample ID	21000		21001		21002		21003		021004D		21004		21005		21006		21007		21008		21009		21020		21021	
Sample Date	4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003		4/17/2003	
Sample Designation	SA		SA		SA		SA		DU		SA		SA		SA		SA		SA		SA		SA		DU	
Parameter	Units	Maximum Detected Value	Action Level	No. of Exceedances	No. of Detections	No. of Samples Analyzed (1)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Benzo(a)anthracene	UG/KG	66600	224	12	12	12	39300 J	4670 J	7690 J	27900 J	1330	1740	11300 J	66600 J	9100 J	3300 J	2660	19400 J								
Benzo(a)pyrene	UG/KG	58900	61	12	12	12	31600 J	3300 J	7240 J	22900 J	1080	1710	11500 J	56900 J	8840 J	3240 J	2100 J	19600 J								
Benzo(b)fluoranthene	UG/KG	102000	1100	12	12	12	56700 J	6340 J	8980 J	28800 J	1670	2510	11900 J	102000 J	12300 J	4050 J	3210 J	22700 J								
Benzo(k)fluoranthene	UG/KG	11700	1100	7	7	12	1370 UJ	3660 J	4340 J	11700 J	41.4 U	34.4 U	5240 J	4060 UJ	5760 J	1540 J	35.5 UJ	11200 J								
Chrysene	UG/KG	67700	400	12	12	12	35000 J	3340 J	7950 J	29900 J	1150	2060	12200 J	67700 J	9480 J	4150 J	2620	20000 J								
Dibenz(a,h)anthracene	UG/KG	19900	14	3	3	12	19900 J	348 UJ	354 UJ	1380 UJ	281	354	384 UJ	4080 UJ	375 UJ	353 UJ	35.5 UJ	358 UJ								
Dibenzofuran	UG/KG	22100	5200	2	12	12	11300 J	250 J	781 J	2210 J	265 J	40.8 J	1750 J	22100 J	2300 J	488 J	46.3 J	5000 J								
Fluoranthene	UG/KG	151000	50000	3	12	12	89900 J	8100 J	17400 J	53200 J	2590	1500	17400 J	151000 J	19400 J	6980 J	2480	34500 J								
Indeno(1,2,3-cd)pyrene	UG/KG	24900	3200	7	12	12	11600 J	2630 J	3640 J	10700 J	572	662	3770 J	24900 J	4020 J	1730 J	864	7020 J								
Naphthalene	UG/KG	33900	13000	1	8	12	838 J	348 UJ	354 UJ	1380 UJ	572	62.7	2030 J	33900 J	2440 J	353 UJ	106	10100 J								
Phenanthrene	UG/KG	159000	50000	2	12	12	81800 J	5340 J	12400 J	38300 J	2000	668	14700 J	159000 J	18800 J	5240 J	1050	34100 J								
Phenol	UG/KG	1680	30	3	3	12	13700 UJ	3480 UJ	3540 UJ	13800 UJ	414 U	344 U	3840 UJ	1680 J	178 J	3530 UJ	355 U	372 J								
Pyrene	UG/KG	148000	50000	3	12	12	98600 J	10500 J	15700 J	61200 J	2150	3280	23500 J	148000 J	18400 J	8150 J	5350	39000 J								
Cadmium	UG/KG	4200	2900	3	12	13	359	134 J	78.8 U	150 J	329	325 J	97.4 J	300 J	4200	470	4200	251 J								
Chromium	UG/KG	52800	32700	3	13	13	6410	8080	7570	10700	52300	52300	5230	8970	30700	39100	11900	17400								
Copper	UG/KG	86400	82800	1	13	13	8110	10600	9500	11400	35100	34300	6230	11600	53800	14100	18900	10700								
Lead	UG/KG	1570000	400000	1	13	13	24700	23400	14800	26800	29300	27600	9510	1570000	372000	62800	77600	141000								
Magnesium	UG/KG	56100000	29100000	8	13	13	19800000	32500000	35700000	37500000	52300000	56700000	56100000	34800000	84500000	65800000	36700000	33900000								
Zinc	UG/KG	752000	126500	4	13	13	28100	36200	29400	63900	156000	151000	30600	56800	782000	328000	78400	88000								

NOTES:  
SA = Sample  
DU = Duplicate  
Q = Data Qualifier  
U = Undetected  
J = Estimated

NOTES:  
(1) - Number of samples analyzed includes all QA/QC samples  
(2) - The 2nd part of the designation identifies the grid location on Figure 2-3 (i.e. SS301-00 = sample #00)



50 FEET LONG



GRID #	FIELD SAMPLE #
4	15001
13	15003,15004
15	15013
16	15002
18	15000
43	15005
47	15006
49	15014
58	15015
63	15007
64	15011
65	15008
77	15012
84	15009
90	15010,15010D
■ EXT	15016
■ EXT2	15017



SCALE: 1"=10'


FIGURE 2-1

SENECA ARMY DEPOT ACTIVITY  
RCRA CLOSURE  
BUILDING 307

RINSATE SAMPLE LOCATIONS

**PARSONS**

290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9560



LEGEND

■ 39 WIPE SAMPLE LOCATIONS



SCALE: 1"=10'


**FIGURE 2-2**

SENECA ARMY DEPOT ACTIVITY  
RCRA CLOSURE  
BUILDING 307

PCB WIPE SAMPLE LOCATIONS

**PARSONS**

290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9550



GRID #	FIELD SAMPLE #
1	25011
4	25015
13	25014
28	25000
30	25013
42	25008
43	25007
47	25002,25003
63	25006
65	25004
68	25001
73	25005
84	25009
90	25010
93	25012



SCALE: 1"=10'

FIGURE 2-3


SENECA ARMY DEPOT ACTIVITY  
RCRA CLOSURE  
BUILDING 301

RINSATE SAMPLE LOCATIONS

**PARSONS**

290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9560





LEGEND

- 01 WIPE SAMPLE LOCATIONS
- ✱ 19 CHIP SAMPLE LOCATIONS



SCALE: 1"=10'


FIGURE 2-4

SENECA ARMY DEPOT ACTIVITY  
RCRA CLOSURE  
BUILDING 301

PCB SAMPLE LOCATIONS

**PARSONS**

290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9560



**LEGEND**

● 01 SURFACE SOIL SAMPLE LOCATIONS



SCALE: 1"=10'


**FIGURE 2-5**

SENECA ARMY DEPOT ACTIVITY  
RCRA CLOSURE  
BUILDING 307

**SOIL SAMPLE LOCATIONS**

**PARSONS**

290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9560



LEGEND

- 01 SURFACE SOIL SAMPLE LOCATIONS



SCALE: 1"=10'

FIGURE 2-6

SENECA ARMY DEPOT ACTIVITY  
RCRA CLOSURE  
BUILDING 301

SOIL SAMPLE LOCATIONS

**PARSONS**

290 ELWOOD DAVIS ROAD, SUITE 312, LIVERPOOL, N.Y. 13088, PHONE: 315-451-9560

## SECTION 3

### DATA ANALYSIS

#### 3.1 BUILDING 307

##### 3.1.1 Rinsate Samples

The analytical results from the rinsate sampling were compared to the NYS GWQS. This Standard was used as a guidance to confirm the degree of decontamination achieved.

The only VOC detected at a concentration greater than the Standard was toluene. Sample 4; 8.4 parts per billion (ppb) and sample 18; 6.7 ppb are less than 4 ppb greater than the 5 ppb Standard. Sample EXT2; 17.2 ppb was collected on the concrete ramp leading into the building, however, the other exterior ramp sample (EXT, collected within 4 feet of EXT2) was non-detect for toluene.

There were two SVOC's that had exceedances of the Standard. Bis(2-Ethylhexyl)phthalate exceeded the Standard in samples 49, 58, 64, 77 and the exterior ramp (8.7, 5.9, 5.6, 7.1 and 10.8 ppb). These results are less than 6 ppb greater than the 5 ppb Standard. Pentachlorophenol exceeded the Standard in samples 18 and 90 (8.9 and 5.9 ppb). These results are less than 8 ppb greater than the 1 ppb Standard.

Four metals (arsenic, cadmium, iron and lead) were detected at concentrations greater than the Standard. The maximum values of arsenic and cadmium detected are less than the Groundwater Effluent Limitation (GEL).

Iron, at a maximum of 3,880 ug/L is not a hazardous constituent and therefore not regulated as part of this decontamination effort.

Lead concentrations at a maximum of 165 ug/L are likely due to migration of dust into the building through the open to the environment, passive ventilation system. Even so, the maximum detected concentration is far below the hazardous waste regulated value of 5,000 ug/L.

##### 3.1.2 PCB Samples

No PCBs were detected.

##### 3.1.3 Soil Samples

The analytical results from the soil sampling were compared to NYS TAGM 4046 guidelines. The purpose was to assess whether grounds surrounding the building had been impacted by waste materials from ongoing operations during the life of this building.

Four SVOCs were detected at concentrations greater than TAGM 4046 guidelines. Benzo(a)anthracene exceeded the guideline in samples 1, 2 and 8 (0.402, 0.514 and 0.291 parts per million (ppm)). Benzo(a)pyrene exceeded the guideline in 11 of 12 samples with a

**PARSONS**

maximum concentration of 0.561 ppm. Benzo(b)fluoranthene exceeded the guideline in sample 2 (1.140 ppm). Chrysene exceeded the guideline in samples 1, 2 and 11 (0.405, 0.591 and 0.427 ppm). All four SVOCs were detected at concentrations less than 1 ppm greater than their respective guideline.

Three metals (calcium, sodium and zinc) were detected at concentrations greater than their respective Senecawide Maximum Background values. However, all three of these metals are non-hazardous by regulatory status. The magnitude of the exceedances is small and is likely due to variations in normal soil background levels.

Mercury was detected at concentrations greater than the Senecawide Maximum Background values in one sample and its duplicate. The detected value is 0.354 ppm. This value is less than 0.5 ppm greater than the Senecawide Maximum Background concentration. The magnitude of the exceedance is negligible and is likely due to variations in normal soil background levels.

## **3.2 BUILDING 301**

### **3.2.1 Rinsate Samples**

The analytical results from the rinsate sampling were compared to the NYS GWQS. This Standard was used as a guidance to confirm the degree of decontamination achieved.

The only VOC detected at a concentration greater than the Standard was 1,1'-Biphenyl. Sample 90, collected on the gravel and tar/asphalt exterior loading dock at 7.7 ppb is less than 3 ppb greater than the 5 ppb Standard.

There were two SVOCs that had exceedances of the Standard. 3 or 4-Methylphenol exceeded the Standard in sample 90 (3.4 ppb) and is less than 3 ppb greater than the 1 ppb Standard. Bis(2-Ethylhexyl)phthalate exceeded the Standard in samples 43 and 63 (12.7 and 9.5 ppb). These results are less than 8 ppb greater than the 5 ppb Standard.

Three metals (cadmium, iron and lead) were detected at concentrations greater than the Standard. The maximum value of cadmium detected is less than the GEL.

Iron, at a maximum of 2,930 ug/L is not a hazardous constituent and therefore not regulated as part of this decontamination effort.

Lead concentrations at a maximum of 1,050 ug/L are likely due to migration of dust into the building from open doorways during sampling. Even so, the maximum detected concentration is far below the hazardous waste regulated value of 5,000 ug/L.

### **3.2.2 PCB Samples**

No PCBs were detected.

### 3.2.3 Soil Samples

The analytical results from the soil sampling were compared to NYS TAGM 4046 guidelines. The purpose was to assess whether grounds surrounding the building had been impacted by waste materials from ongoing operations during the life of this building.

There were no VOC exceedances of the TAGM 4046 guidelines.

Thirteen SVOCs were detected at concentrations greater than TAGM 4046 guidelines. Benzo(a)anthracene, benzo(b)pyrene, benzo(b)fluoranthene and chrysene exceeded the guidelines in all 12 samples collected. Benzo(k)fluoranthene, dibenz(a,h)anthracene, dibenzofuran, fluoranthene, indeno(1,2,3-cd)pyrene, naphthalene, phenanthrene, phenol and pyrene exceeded the guidelines with less frequency. SVOC concentrations above TAGM 4046 guidelines are typically seen in industrial areas. Building 301 is situated directly adjacent to a railroad spur (Figure 1). Dust from the railroad operations is the likely source of the SVOC exceedances.

Four metals (cadmium, copper, magnesium and zinc) were detected at concentrations greater than the Senecawide Maximum Background value. However, all three of these metals are non-hazardous by regulatory status. The magnitude of the exceedances is small and is likely due to variations in normal soil background levels.

Lead exceeded the EPA residential standard of 400 ppm in one of twelve sample locations. Sample 7 (1,570 ppm). This level is considered normal for an industrial area.

Chromium was detected at concentrations marginally greater than Senecawide Maximum Background value in two of twelve locations (three samples total including one duplicate). The detected values are 52.8 and 39.1 ppm. The Senecawide Maximum Background concentration is 32.7 ppm. The magnitude of the exceedance is negligible and is likely due to variations in normal soil background levels.

## 3.3 CONCLUSIONS

### 3.3.1 Building 307

- Building 307 is free of all PCB contamination.
- Generally, the decontamination effort removed all visible contamination and produced non-hazardous rinsewater for disposal. Despite the minor exceedances of the GWQS in the confirmatory rinsate samples, it can be concluded that the building is sufficiently decontaminated.
- Soil sample results are in general what might be expected in an industrial setting. It does not appear that waste storage operations caused any impact to the surrounding soils.

### 3.3.2 Building 301

- Building 301 is free of all PCB contamination.

---

**PARSONS**

- Generally, the decontamination effort removed all visible contamination and produced non-hazardous rinsewater for disposal. Despite the minor exceedances of the GWQS in the confirmatory rinsate samples, it can be concluded that the building is sufficiently decontaminated.
- Soil sample results are generally what would be expected in an industrial setting. It does not appear that waste storage operations caused any impact to the surrounding soils.

### **3.4 RECOMMENDATIONS**

- No further decontamination efforts are required. The confirmatory sampling shows a sufficient degree of decontamination was achieved.
- Close SEAD-1 and SEAD-2 with regulatory concurrence.

**APPENDIX A**  
**ANALYTICAL RESULTS**

**Table A-1 Building 307 Rinsate Samples**

**Table A-2 Building 307 PCB Wipe Samples**

**Table A-3 Building 301 Rinsate Samples**

**Table A-4 Building 301 PCB Wipe Samples**

**Table A-5 Building 301 PCB Chip Samples**

**Table A-6 Building 307 Soil Samples**

**Table A-7 Building 301 Soil Samples**

**Table A-8 Washwater for Disposal**

*(Tables A-1 through A-8 contain summarized analytical results. Full data reports are included on the attached disk).*







**SEAD-1(BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1
Sample Number			W307-00	W307-01	W307-02	W307-03	W307-04	W307-05	W307-06	
Sample Type			WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	
Field Sample ID			16000	16001	16002	16003	16004	16005	16006	
Sample Date			4/21/2003	4/21/2003	4/21/2003	4/21/2003	4/21/2003	4/21/2003	4/21/2003	
Sample Designation			SA	SA	SA	SA	SA	SA	SA	
Parameter	Units	Action Level	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Aroclor-1016	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1221	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1232	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1242	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1248	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1254	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1260	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U

**NOTES:**

SA = Sample  
 FB = Field Blank  
 Q = Data Qualifier  
 U = Undetected

**SEAD-1 (BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1	
Sample Number			W307-07		W307-08		W307-09		W307-10		W307-11		W307-12		W307-13	
Sample Type			WIPE		WIPE		WIPE		WIPE		WIPE		WIPE		WIPE	
Field Sample ID			16007		16008		16009		16010		16011		16012		16013	
Sample Date			4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/21/2003	
Sample Designation			SA		SA		SA		SA		SA		SA		SA	
Parameter	Units	Action Level	Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)	
Aroclor-1016	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1221	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1232	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1242	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1248	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1254	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1260	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U	

**NOTES:**

SA = Sample

FB = Field Blank

Q = Data Qualifier

U = Undetected

**SEAD-1 (BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1	
Sample Number			W307-14		W307-15		W307-16		W307-17		W307-18		W307-19		W307-20	
Sample Type			WIPE		WIPE		WIPE		WIPE		WIPE		WIPE		WIPE	
Field Sample ID			16014		16015		16016		16017		16018		16019		16020	
Sample Date			4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/21/2003	
Sample Designation			SA		SA		SA		SA		SA		SA		SA	
Parameter	Units	Action Level	Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)	
Aroclor-1016	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Aroclor-1221	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Aroclor-1232	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Aroclor-1242	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Aroclor-1248	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Aroclor-1254	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Aroclor-1260	UG/Filter	10	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U

**NOTES:**

SA = Sample  
 FB = Field Blank  
 Q = Data Qualifier  
 U = Undetected

**SEAD-1 (BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		
Sample Number			W307-21		W307-22		W307-23		W307-24		W307-25		W307-26		W307-27
Sample Type			WIPE		WIPE		WIPE		WIPE		WIPE		WIPE		WIPE
Field Sample ID			16021		16022		16023		16024		16025		16026		16027
Sample Date			4/21/2003		4/21/2003		4/21/2003		4/21/2003		4/22/2003		4/22/2003		4/22/2003
Sample Designation			SA		SA		SA		SA		SA		SA		SA
Parameter	Units	Action Level	Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)
Aroclor-1016	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U
Aroclor-1221	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U
Aroclor-1232	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U
Aroclor-1242	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U
Aroclor-1248	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U
Aroclor-1254	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U
Aroclor-1260	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U

**NOTES:**

SA = Sample  
 FB = Field Blank  
 Q = Data Qualifier  
 U = Undetected

**SEAD-1 (BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		SEAD-1		
Sample Number			W307-28		W307-29		W307-30		W307-31		W307-32		W307-33		W307-34
Sample Type			WIPE		WIPE		WIPE		WIPE		WIPE		WIPE		WIPE
Field Sample ID			16028		16029		16030		16031		16032		16033		16034
Sample Date			4/22/2003		4/22/2003		4/22/2003		4/22/2003		4/22/2003		4/22/2003		4/22/2003
Sample Designation			SA		SA		SA		SA		SA		SA		SA
Parameter	Units	Action Level	Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)		Value (Q)
Aroclor-1016	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 UJ
Aroclor-1221	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 UJ
Aroclor-1232	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 UJ
Aroclor-1242	UG/Filter	10	0.1 U		0.1 U		0.96 U		0.1 U		0.1 U		0.1 U		0.1 UJ
Aroclor-1248	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 UJ
Aroclor-1254	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 UJ
Aroclor-1260	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 U		0.1 UJ

**NOTES:**

- SA = Sample
- FB = Field Blank
- Q = Data Qualifier
- U = Undetected

**SEAD-1 (BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1	SEAD-1
Sample Number			W307-35	W307-36	W307-37	W307-38	W307-39	W307-40	W307-41	
Sample Type			WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE
Field Sample ID			16035	16036	16037	16038	16039	16040	16041	
Sample Date			4/22/2003	4/22/2003	4/22/2003	4/22/2003	4/22/2003	4/23/2003	4/23/2003	
Sample Designation			SA	SA	SA	SA	SA	SA	SA	SA
Parameter	Units	Action Level	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Aroclor-1016	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1221	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1232	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1242	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1248	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1254	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1260	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U

**NOTES:**

SA = Sample

FB = Field Blank

Q = Data Qualifier

U = Undetected



**SEAD-1 (BLDG 307)  
INTERIOR SURFACES  
PCB WIPE SAMPLE DATA**

Location ID			SEAD-1		SEAD-1		SEAD-1		SEAD-1	
Sample Number			W307-42		W307-RB		W307-RB		W307-RB	
Sample Type			WIPE		WIPE		WIPE		WIPE	
Field Sample ID			16042		16043		16044		16045	
Sample Date			4/23/2003		4/21/2003		4/22/2003		4/22/2003	
Sample Designation			SA		FB		FB		FB	
Parameter	Units	Action Level	Value (Q)		Value (Q)		Value (Q)		Value (Q)	
Aroclor-1016	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1221	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1232	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1242	UG/Filter	10	0.1 U		0.1 U		2.4 U		0.1 U	
Aroclor-1248	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1254	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U	
Aroclor-1260	UG/Filter	10	0.1 U		0.1 U		0.1 U		0.1 U	

**NOTES:**

SA = Sample

FB = Field Blank

Q = Data Qualifier

U = Undetected



SEAD-2 (BLDG 301)  
 INTERIOR SURFACES  
 PCB WIPE SAMPLE DATA

Location ID		SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2
Sample Number		W301-10	W301-11	W301-12	W301-13	W301-14	W301-15	W301-23	W301-24	
Sample Type		WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	
Field Sample ID		26010	26011	26012	26013	26014	26015	26023	26024	
Sample Date		4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	
Sample Designation		SA	SA	SA	SA	SA	SA	SA	RB	RB
Parameter	Units	Action Level	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Aroclor-1016	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1221	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1232	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1242	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1248	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1254	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1260	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U

**NOTES:**

- SA = Sample
- DU = Duplicate
- RB = Rinse Blank
- Q = Data Qualifier
- U = Undetected

Location ID			SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2
Sample Number			W301-16	W301-17	W301-18	W301-19	W301-20	W301-21	W301-22
Sample Type			CHIP	CHIP	CHIP	CHIP	CHIP	CHIP	CHIP
Field Sample ID			26016	26017	26018	26019	26020	26021	26022
Sample Date			4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003
Sample Designation			SA	SA	SA	SA	SA	SA	DU
Parameter	Units	Action Level	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Aroclor-1016	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1221	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1232	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1242	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1248	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1254	UG/KG	1000	1000 U	388 J	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1260	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1262	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U
Aroclor-1268	UG/KG	1000	1000 U	1000 U	1000 U	1020 U	1020 U	1030 U	1030 U

**NOTES:**

- SA = Sample
- DU = Duplicate
- (Q) = Data Qualifier
- U = Undetected
- J = Estimated Value



SEAD-2 (BLDG 301)  
RINSEATE SAMPLE DATA  
ALL COMPOUNDS

Table with columns for Location ID, Sample Type, Field Sample ID, Sample Date, and 20 Rinseate samples (SEAD-2 R301-1 to R301-93). Each sample column includes SA (Sample Area) and DU (Duplicate) values. The main data columns are: Parameter, Units, Max, Freq, Level, Ex, Det, No., and Value (Q) for each of the 20 samples.

NOTES:

SA = Sample  
DU = Duplicate  
Maximum = Maximum Detected Value  
Freq = Frequency of Detection  
Level = Action Level or Cleanup Criteria  
Ex = Number of Exceedances of the Action Level  
Det = Number of Detections

NOTES:

Q = Data Qualifier  
U = Undetected  
J = Estimated

SEAD-2 (BLDG 301)  
 INTERIOR SURFACES  
 PCB WIPE SAMPLE DATA

Location ID			SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2	SEAD-2
Sample Number			W301-00	W301-01	W301-02	W301-03	W301-04	W301-05	W301-06	W301-07	W301-08	W301-09	W301-09	W301-09	W301-09
Sample Type			WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE	WIPE
Field Sample ID			26000	26001	26002	26003	26004	26005	26006	26007	26008	26009	26009	26009	26009
Sample Date			4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003	4/24/2003
Sample Designation			SA	SA	SA	SA	SA	SA	SA	SA	SA	SA	SA	SA	SA
Parameter	Units	Action Level	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
Aroclor-1016	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 UJ	0.1 UJ	0.1 U	0.1 UJ	0.1 UJ
Aroclor-1221	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1232	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 UJ	0.1 UJ	0.1 U	0.1 UJ	0.1 UJ
Aroclor-1242	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 UJ	0.1 UJ	0.1 U	0.1 UJ	0.1 UJ
Aroclor-1248	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1254	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Aroclor-1260	UG/Filter	10	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U

NOTES:

- SA = Sample
- DU = Duplicate
- RB = Rinse Blank
- Q = Data Qualifier
- U = Undetected











Location ID			SEAD-1	SEAD-2	SEAD-2
Building ID/Location			307/Drum	301/Drum	301/Drum
Sample Type			WATER	WATER	WATER
Sample Number			307	301D	301
Sample Date			4/21/2003	4/21/2003	4/21/2003
Sample Designation			SA	DU	SA
			BUILDING 301	BUILDING 307	BUILDING 307
Parameter	Units	Regulatory Level	Value (Q)	Value (Q)	Value (Q)
1,1,1-Trichloroethane	UG/L		1 U		50 U
1,1,2,2-Tetrachloroethane	UG/L		1 U		50 U
1,1,2-Trichloroethane	UG/L		1 U		50 U
1,1-Dichloroethane	UG/L		1 U		50 U
1,1-Dichloroethene	UG/L		1 U		50 U
1,2-Dichloroethane	UG/L	500	1 U		50 U
1,2-Dichloropropane	UG/L		1 U		50 U
Acetone	UG/L		138 J		250 U
Benzene	UG/L	500	1 UJ		50 UJ
Bromodichloromethane	UG/L		1 U		50 U
Bromoform	UG/L		1 U		50 U
Carbon disulfide	UG/L		5 U		250 U
Carbon tetrachloride	UG/L	500	1 U		50 U
Chlorobenzene	UG/L	100000	1 UJ		50 UJ
Chlorodibromomethane	UG/L		1 U		50 U
Chloroethane	UG/L		1 UJ		50 UJ
Chloroform	UG/L	6000	1 U		50 U
Cis-1,2-Dichloroethene	UG/L		1 U		50 U
Cis-1,3-Dichloropropene	UG/L		1 U		50 U
Ethyl benzene	UG/L		1 UJ		50 UJ
Methyl bromide	UG/L		1 UJ		50 UJ
Methyl butyl ketone	UG/L		5 U		250 U
Methyl chloride	UG/L		1 UJ		50 UJ
Methyl ethyl ketone	UG/L	200000	5 U		250 U
Methyl isobutyl ketone	UG/L		5 U		250 U
Methylene chloride	UG/L		5 UJ		250 UJ
Styrene	UG/L		1 UJ		50 UJ
Tetrachloroethene	UG/L		1 U		50 U
Toluene	UG/L		0.47 J		50 UJ
Total Xylenes	UG/L		1 UJ		50 UJ
Trans-1,2-Dichloroethene	UG/L		1 U		50 U
Trans-1,3-Dichloropropene	UG/L		1 U		50 U
Trichloroethene	UG/L		1 U		50 U
Vinyl acetate	UG/L		5 UJ		250 UJ
Vinyl chloride	UG/L	200	1 U		50 U
1,1'-Biphenyl	UG/L		9.7 U		99 U
1,2,4-Trichlorobenzene	UG/L		9.7 U		99 U
1,2-Dichlorobenzene	UG/L		9.7 U		99 U
1,3-Dichlorobenzene	UG/L		9.7 U		99 U
1,4-Dichlorobenzene	UG/L	7500	9.7 U		99 U
2,4,5-Trichlorophenol	UG/L	400000	9.7 U		99 U
2,4,6-Trichlorophenol	UG/L	2000	9.7 U		99 U
2,4-Dichlorophenol	UG/L		9.7 U		99 U
2,4-Dimethylphenol	UG/L		9.7 U		99 U
2,4-Dinitrophenol	UG/L		19.4 U		198 U
2,4-Dinitrotoluene	UG/L	130	9.7 U		99 U
2,6-Dinitrotoluene	UG/L		9.7 U		99 U
2-Chloronaphthalene	UG/L		0.97 U		9.9 U
2-Chlorophenol	UG/L		9.7 U		99 U
2-Methylnaphthalene	UG/L		0.97 U		7 NJ
2-Methylphenol	UG/L		9.7 U		99 U
2-Nitroaniline	UG/L		9.7 U		99 U
2-Nitrophenol	UG/L		9.7 U		99 U
3 or 4-Methylphenol	UG/L		9.7 U		99 U
3,3'-Dichlorobenzidine	UG/L		9.7 U		99 U



Location ID			SEAD-1		SEAD-2		SEAD-2	
Building ID/Location			307/Drum		301/Drum		301/Drum	
Sample Type			WATER		WATER		WATER	
Sample Number			307		301D		301	
Sample Date			4/21/2003		4/21/2003		4/21/2003	
Sample Designation			SA		DU		SA	
			BUILDING 301		BUILDING 307		BUILDING 307	
Parameter	Units	Regulatory Level	Value (Q)		Value (Q)		Value (Q)	
3-Nitroaniline	UG/L		9.7 U				99 U	
4,6-Dinitro-2-methylphenol	UG/L		9.7 U				99 U	
4-Bromophenyl phenyl ether	UG/L		9.7 U				99 U	
4-Chloro-3-methylphenol	UG/L		9.7 U				99 U	
4-Chloroaniline	UG/L		9.7 U				99 U	
4-Chlorophenyl phenyl ether	UG/L		9.7 U				99 U	
4-Nitroaniline	UG/L		9.7 U				99 U	
4-Nitrophenol	UG/L		9.7 U				99 U	
Acenaphthene	UG/L		0.97 U				7.1 J	
Acenaphthylene	UG/L		0.97 U				9.9 U	
Anthracene	UG/L		0.97 U				122 NJ	
Atrazine	UG/L		9.7 U				99 U	
Benzaldehyde	UG/L		9.7 U				99 U	
Benzo(a)anthracene	UG/L		0.97 U				14.5 NJ	
Benzo(a)pyrene	UG/L		0.97 U				11.8 NJ	
Benzo(b)fluoranthene	UG/L		0.97 U				17.1	
Benzo(ghi)perylene	UG/L		0.97 U				9.9 U	
Benzo(k)fluoranthene	UG/L		0.97 U				9.9 U	
Bis(2-Chloroethoxy)methane	UG/L		9.7 U				99 U	
Bis(2-Chloroethyl)ether	UG/L		9.7 U				99 U	
Bis(2-Chloroisopropyl)ether	UG/L		9.7 U				99 U	
Bis(2-Ethylhexyl)phthalate	UG/L		2.9 J				20.9 J	
Butylbenzylphthalate	UG/L		9.7 U				99 U	
Carbazole	UG/L		9.7 U				11.5 J	
Chrysene	UG/L		0.97 U				14.8 NJ	
Di-n-butylphthalate	UG/L		9.7 U				13.4 J	
Di-n-octylphthalate	UG/L		9.7 U				99 U	
Dibenz(a,h)anthracene	UG/L		0.97 U				9.9 U	
Dibenzofuran	UG/L		9.7 U				10.1 NJ	
Diethyl phthalate	UG/L		9.7 U				99 U	
Dimethylphthalate	UG/L		0.52 J				99 U	
Diphenylamine	UG/L		9.7 U				99 U	
Fluoranthene	UG/L		0.97 U				44.2	
Fluorene	UG/L		0.97 U				10.4 NJ	
Hexachlorobenzene	UG/L	130	9.7 U				99 U	
Hexachlorobutadiene	UG/L	500	9.7 U				99 U	
Hexachlorocyclopentadiene	UG/L		9.7 U				99 U	
Hexachloroethane	UG/L		9.7 U				99 U	
Indeno(1,2,3-cd)pyrene	UG/L		0.97 U				9.9 U	
Isophorone	UG/L		9.7 U				99 U	
N-Nitrosodipropylamine	UG/L		9.7 U				99 U	
Naphthalene	UG/L		0.97 U				19.6	
Nitrobenzene	UG/L	2000	9.7 U				99 U	
Pentachlorophenol	UG/L	100000	25.5				99 U	
Phenanthrene	UG/L		0.97 U				57.9	
Phenol	UG/L		9.7 U				10.8 J	
Pyrene	UG/L		0.97 U				30.8	
alpha-Terpineol	UG/L		9.7 U				99 U	
Aroclor-1016	UG/L		0.098 U				0.098 R	
Aroclor-1221	UG/L		0.098 U				0.098 R	
Aroclor-1232	UG/L		0.098 U				0.098 R	
Aroclor-1242	UG/L		2.2				0.098 R	
Aroclor-1248	UG/L		0.098 U				0.098 R	
Aroclor-1254	UG/L		0.66				0.098 R	
Aroclor-1260	UG/L		0.098 U				0.098 R	

Location ID			SEAD-1	SEAD-2	SEAD-2
Building ID/Location			307/Drum	301/Drum	301/Drum
Sample Type			WATER	WATER	WATER
Sample Number			307	301D	301
Sample Date			4/21/2003	4/21/2003	4/21/2003
Sample Designation			SA	DU	SA
			BUILDING 301	BUILDING 307	BUILDING 307
Parameter	Units	Regulatory Level	Value (Q)	Value (Q)	Value (Q)
Aroclor-1262	UG/L		0.098 U		0.098 R
Aroclor-1268	UG/L		0.098 U		0.098 R
Aluminum	UG/L		1160 J	2380 J	2220 J
Antimony	UG/L		2.63 UJ	2.63 UJ	4.05 J
Arsenic	UG/L	5000	9.55 J	1210 J	1220 J
Barium	UG/L	100000	27.3 J	58.6 J	55.3 J
Beryllium	UG/L		0.16 UJ	0.16 UJ	0.16 UJ
Boron	UG/L		557 J	327 J	328 J
Cadmium	UG/L	1000	1.43 J	14.9 J	14.9 J
Calcium	UG/L		59500 J	164000 J	166000 J
Chromium	UG/L	5000	14.8 J	17.9 J	17.1 J
Cobalt	UG/L		0.65 J	9.97 J	9.99 J
Copper	UG/L		26.2 J	140 J	140 J
Iron	UG/L		9360 J	9340 J	9000 J
Lead	UG/L	5000	65.4 J	4590 J	4490 J
Magnesium	UG/L		13000 J	23500 J	23600 J
Manganese	UG/L		124 J	258 J	255 J
Mercury	UG/L	200	0.302 J	0.052 UJ	0.054 J
Molybdenum	UG/L		7.02 J	20.3 J	20.3 J
Nickel	UG/L		8.94 J	40.4 J	40.5 J
Phosphorous	UG/L		244 J	6370 J	6340 J
Potassium	UG/L		12800 J	188000 J	191000 J
Selenium	UG/L	1000	17.8 J	34.7 J	37.8 J
Silica	UG/L		6870 J	34200 J	37900 J
Silicon	UG/L		3140 J	15600 J	17300 J
Silver	UG/L		1.57 J	6.84 J	6.9 J
Sodium	UG/L		97200 J	209000 J	211000 J
Strontium	UG/L		250 J	470 J	474 J
Sulfur	UG/L		19900 J	186000 J	181000 J
Thallium	UG/L		7.18 J	9.39 J	10.4 J
Tin	UG/L		53.7 UJ	21.5 UJ	21.5 UJ
Titanium	UG/L		17.5 J	49.9 J	46.5 J
Uranium	UG/L		4.98 UJ	4.98 UJ	4.98 UJ
Vanadium	UG/L		3.95 J	129 J	130 J
Zinc	UG/L		1090 J	2200 J	2180 J
<b>NOTES:</b>					
SA = Sample			The drummed washwater is non-hazardous by		
FB = Field Blank			characteristics for off-site disposal purposes.		
TB = Trip Blank					
(Q) = Data Qualifier					
U = Undetected					
J = Estimated Value					
UJ =					
NJ =					
Deleted Compound					

**APPENDIX B**  
**DISPOSAL DOCUMENTATION**

---

**PARSONS**

PA743157 SENECA BLDG 307, 301 CLOSURE RPT SEP 03.DOC  
SEPTEMBER 4, 2003

**THIS MEMORANDUM** is an acknowledgement that a bill of lading has been issued and is not the Original Bill of Lading, not a copy or duplicate, covering the property named herein, and is intended solely for filing or record.

To: DAN Hoffner From: Vonne Walseman Shipper's No. SAD030619

Carrier: INDUSTRIAL OIL TANK SVC CORP. SCAC: \_\_\_\_\_ Carrier's No. 6A-282  
 received, subject to the classifications and tariffs in effect on the date of this Bill of Lading:

at IOTSC date 6/19/03 from Seneca Army Depot

the property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below, which said company (the word company being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its own road or its own water line, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed, as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any of said property, that every service to be performed hereunder shall be subject to all the conditions not prohibited by law, whether printed or written, herein contained (as specified in Appendix B to Part 1035) which are hereby agreed to by the shipper and accepted for himself and his assigns.

TO: (Mail or street address of consignee for purposes of notification only.)		FROM:	
Consignee <u>INDUSTRIAL OIL TANK SVC CORP.</u>		Shipper <u>Seneca Army Depot</u>	
Street <u>120 DRY RD.</u>		Street <u>Route 96</u>	
Destination <u>ORISKANY, NY</u> Zip <u>13424</u>		Origin <u>Romulus, NY</u> Zip _____	
Route: <u>NYR000005298</u>			

Delivering Carrier <u>INDUSTRIAL OIL TANK SVC CORP.</u>	Trailer Initial/Number <u>TK12</u>	U.S. DOT. Hazmat Reg. Number <u>256099</u>
--	---------------------------------------	---

No. of Packages	H/M	Description of articles, special marks, and exceptions	Hazard Class	I.D. Number	Packing Group	*Weight (subject to correction)	Class or rate	Labels required (or exemption)	Check column
0		<u>NON-RCRA/NON-DOT Regulated Material</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>500 #/leg.</u>			
		<u>Time left:</u>	<u>7:00</u>						
		<u>Time arrive:</u>	<u>9:15</u>						
		<u>Time depart:</u>	<u>9:45</u>						
		<u>Time @ shop:</u>	<u>12:00</u>						

Remit C.O.D. to: Address: City: _____ State: _____ Zip: _____	<b>COD AMT:</b> \$ _____ Charges Advanced \$ _____	Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges.  (Signature of consignor)	<b>C. O. D. FEE:</b> Prepaid <input type="checkbox"/> Collect <input type="checkbox"/> \$ _____ <b>FREIGHT CHARGES</b> <input type="checkbox"/> Prepaid <input type="checkbox"/> Collect
<small>The shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's or shipper's weight". Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property. An agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding _____ per _____.</small>	<b>PLACARDS REQUIRED</b> <u>NO</u>	<b>PLACARDS SUPPLIED</b> <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO - FURNISHED BY CARRIER	<b>DRIVER'S SIGNATURE:</b> _____

**SPECIAL INSTRUCTIONS:**

SHIPPER: Seneca Army Depot CARRIER: INDUSTRIAL OIL TANK SERVICE CORP.  
 PER: [Signature] DATE: 6/19/03 PER: [Signature] DATE: 6/19/03  
 EMERGENCY RESPONSE TELEPHONE NUMBER: (315) 736-6080  
Monitored at all times the Hazardous Material is in transportation including storage incidental to transportation (§172.604).



# INDUSTRIAL OIL TANK SERVICE CORP.

VACUUM TRUCK & TRANSPORTATION SERVICES  
WASTE DISPOSAL - PETROLEUM RECYCLING  
REMEDICATION SUPPLIES

120 Dry Road  
Oriskany, New York 13424  
Telephone: (315) 736-8080  
Fax: (315) 736-4649

EPA NO. NYR000005298

PLEASE ATTACH: Air Material Safety Data Sheets, MSDS's, Analytic Reports, Handling Procedures, Appropriate Information, Spill Kit Data & Comments

Company Name SENZA Army Depot Activity  
 Facility Address ROUTE 96  
 City, State, Zip Romulus NY 14541  
 Technical Contact STEVE ABSOLON  
 (Name) (Title)  
 Area Code (607) Telephone # 869-1309  
 Facility EPA ID # N/A

Billing Address 153 Brooks Road  
BLDG 201 GAFB  
 City, State, Zip ROMULUS NY 13441  
 Business Contact RICH STAPLETON  
 (Name) (Title)  
 Area Code (315) Telephone # 336-2100  
 Common Name of Waste NON HAZ PPE

~~SPECIFIC HAZARD INFORMATION~~  
PPE GENERATED FROM PRESSURE  
WASTING INTERIOR OF 2 BUILDINGS

EPA Reg. Waste No. N/A RCRA No. \_\_\_\_\_  
 Container Type (M) Drum ( ) Bulk ( ) Other \_\_\_\_\_  
 Rate of Generation: 2 DRUMS OF SOLID PPE  
 Quantity Units Per (M/Yr)

~~CRITICAL CONSTITUTIONS~~

<u>SOLIDS</u>	<u>99%</u>	<u>100%</u>
<u>Liquid</u>	<u>0%</u>	<u>1%</u>

Proper NOT Shipping Name: Include HQ Information  
NOT REGULATED  
 Add'l Desc: \_\_\_\_\_  
 Hazard Class N/A UN/NA No. N/A

~~PHYSICAL DESCRIPTION~~  
 Physical State ( ) Liquid ( ) Semi Solid (X) Solid  
 Viscosity (X) Low ( ) Medium ( ) High  
 Liquid Layering (X) None ( ) Layered ( ) Multilayered  
 Solids (Net): MS-M 100% Total \_\_\_\_\_  
 Free Liquid ( ) Yes (X) No  
 Odor None Color None

**Classification:**  
 I hereby certify that I have personally inspected and am familiar with the information contained on this and all attached documents. Based on my inquiry of those individuals primarily responsible for obtaining the information, I believe that the foregoing information is true, accurate, and complete to the best of my knowledge and that all known and suspected hazards have been disclosed.

Steve Absolon 6-11-03  
 Signature Date

Total Halogen (Z) NONE IDC (ppm) \_\_\_\_\_  
 Flash Point 2200 BTU/lb NA  
 PCB (ppm) NONE Pesticide/Herbicide (ppm) NONE

Approved For Acceptance: ( ) Yes ( ) No  
 \_\_\_\_\_  
 Piles Rep. \_\_\_\_\_  
 Handling Code \_\_\_\_\_ Date \_\_\_\_\_

~~HEAVY METALS~~  
\* NONE FOR ALL

	Total	TCLP	Total	TCLP
Antimony (Sb)			Lead (Pb)	
Argenic (As)			Mercury (Hg)	
Barium (Ba)			Nickel (Ni)	
Beryllium (Be)			Selenium (Se)	
Cadmium (Cd)			Silver (Ag)	
Chromium (Cr)			Thallium (Tl)	
Copper (Cu)			Zinc (Zn)	

SEE ATTACHED ANALYTICALS + COC

# INDUSTRIAL OIL TANK SERVICE CORP.

VACUUM TRUCK & TRANSPORTATION SERVICES  
WASTE DISPOSAL - PETROLEUM RECYCLING  
REMEDATION SUPPLIES

120 Dry Road  
Oriskany, New York 13424  
Telephone: (315) 735-6080  
Fax: (315) 736-4649

EPA NO. NYR000005298

PLEASE ATTACH: An updated Safety Data Sheet, MSDS, Analysis Report, Handling Procedures, Administrative Information, Support Data & Comments

Generator Name Seneca Army Depot Activity  
 Facility Address Route 96  
 City, State, Zip Rome, NY 14541  
 Technical Contact STEVE ABSOLON  
(Name) (Title)  
 Area Code 607, Telephone # 869-1309  
 Facility EPA ID # N/A  
 RECEIPT: SPECIAL PROCESS INFORMATION Generated from pressure washing interior walls + floor of 2 buildings

Billing Address 153 Brooks Road  
Bldg 301 GAFB  
 City, State, Zip Rome NY 13441  
 Business Contact Rich Stapleton Superintendent  
or Yvonne Welton (Name) (Title)  
 Area Code (315) Telephone # 336-2100  
 Common Name of Waste Non-hazardous Waste Water  
 EPA Haz. Waste No. N/A RCRA No. N/A  
 Container Type  Drums  Bulk  Other  
 Date of Generation: 8 DRUMS OF LIQUID  
Quantity Units Per (No./Vol)  
 Proper DOT Shipping Name: Exclude (N) Information

ORGANIC CONSTITUENT (CAS No.)	Concentration
<u>Water</u>	<u>99-100%</u>
<u>SOLIDS</u>	<u>0%-1%</u>

Add'l Desc: N/A  
 Hazard Class N/A UN/NA No. N/A  
 PHYSICAL DESCRIPTION  
 Physical State  Liquid  Semi Solid  Solid  
 Viscosity  Low  Medium  High  
 Liquid Layering  None  Bilayered  Multilayered  
 Solids (wt%): None Total    
 Free Liquid  Yes  No  
 Odor NONE Color    
 Total Halogen (Cl) 0% TOC (ppm)    
 Flash Point >200 BTU/lb None  
 PCB (ppm) <1% Pesticide/Herbicide (ppm) <1%

**CERTIFICATION:**  
 I hereby certify that I have personally examined and am familiar with the information submitted on this and all attached documents. Based on my inquiry of those individuals immediately responsible for gathering the information, I believe that the submitted information is true, accurate, and complete to the best of my knowledge and belief and that all known and suspected hazards have been disclosed.  
Thomas Thurl 6-11-03  
Signature Date

Name of Customer \_\_\_\_\_ Date \_\_\_\_\_

Approved for Acceptance:  Yes  No  
 Julian Ray \_\_\_\_\_  
 Handling Code \_\_\_\_\_ Date \_\_\_\_\_

mg/L	TCF	Total	TCF
Antimony (Sb)	<u>4.050</u>	Lead (Pb)	<u>449.0</u>
Arsenic (As)	<u>9550</u>	Mercury (Hg)	<u>0.702</u>
Barium (Ba)	<u>55.3</u>	Nickel (Ni)	<u>40.5</u>
Beryllium (Be)	<u>0.160</u>	Selenium (Se)	<u>37.8</u>
Cadmium (Cd)	<u>14.9</u>	Silver (Ag)	<u>6.900</u>
Chromium (Cr)	<u>17.1</u>	Tin (Sn)	<u>10.4</u>
Copper (Cu)	<u>140</u>	Zinc (Zn)	<u>250</u>

See attached analytical RESULTS + COC

**APPENDIX C**  
**DAILY FIELD REPORTS**

---

**PARSONS**

P:\743157 SENECABLDG 307, 301 CLOSURE RPT SEP 03.DOC  
SEPTEMBER 4, 2003

C-1

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Monday, April 14, 2003
CONTRACT		REPORT NO.	4/14/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50~65
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
Power Washer/Steamer		1	Yvonne Walseman	10
Air Compressor, 185 cfm		1	Jim Goldrick	10
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Mobilized equipment and personnel to site.
- Removed government spill control materials from Bldg 307 and staged in area designated by client representatives.
- Established exclusion zones for each location.
- Applied water for dust suppression and removed oversize debris from floors of Bldgs 301 and 307. Placed collected debris in drum.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

--	--	--

Accidents reported today:	0	Accidents to date:	0
---------------------------	---	--------------------	---

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/14/03	DATE	April 14, 2003
----------	----------------------	------------	---------	------	----------------



Building 307 after debris removal.



Building 301 after debris removal.

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Tuesday, April 15, 2003
CONTRACT		REPORT NO.	4/15/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50≈75
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
Power Washer/Steamer		1	Jim Goldrick	10
Air Compressor, 185 cfm		1		
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Setup washing equipment at Bldg 301.
- Detergent washed walls and floors. Collected rinsate and placed into drums.
- Rinsed walls and floors with clean water three times. Collected rinsate and placed into drums. Approximately 130 gallons of rinsate was collected.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

Dan Hoffner	PARSONS	QC
-------------	---------	----

<b>Accidents reported today:</b>	<b>0</b>	<b>Accidents to date:</b>	<b>0</b>
----------------------------------	----------	---------------------------	----------

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/15/03	DATE	April 15, 2003
----------	----------------------	------------	---------	------	----------------



Performing cleaning operations at Bldg 301.



After completion of rinsing operations.

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Wednesday, April 16, 2003
CONTRACT		REPORT NO.	4/16/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	60=40
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
Power Washer/Steamer		1	Jim Goldrick	10
Air Compressor, 185 cfm		1		
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Setup washing equipment at Bldg 307.
- Placed rinsate collection equipment beneath walls to collect rinsate outside of building.
- Detergent washed walls and collected rinsate and placed into drums.
- Detergent washed floors and collected rinsate and placed into drums. Applied degreaser to stained areas. Floor coating is discolored, concrete beneath is not discolored.
- Rinsed walls and floors with clean water three times. Collected rinsate and placed into drums. Approximately 230 gallons of rinsate was collected.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

Bill Bradford Dan Hoffner	PARSONS PARSONS	H&S Audit QC
------------------------------	--------------------	-----------------

<b>Accidents reported today:</b>	<b>0</b>	<b>Accidents to date:</b>	<b>0</b>
----------------------------------	----------	---------------------------	----------



JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/16/03	DATE	April 16, 2003
----------	----------------------	------------	---------	------	----------------



Collecting rinsate from wall washing



Washing inside of Bldg 307.

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Thursday, April 17, 2003
CONTRACT		REPORT NO.	4/17/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	35=50
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
Power Washer/Steamer		1	Jim Goldrick	10
Air Compressor, 185 cfm		1		
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Prepared for soil sampling at Bldg 301.
- Established soil sample locations outside of building. Existing conditions contain asphalt materials associated with roadway pavements and railroad track beds to include railroad ties located within 2'0" of the building.  
Collected 12 surface soil samples.
- Secured sites for the evening.


**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

--	--	--

<b>Accidents reported today:</b>	<b>0</b>	<b>Accidents to date:</b>	<b>0</b>
----------------------------------	----------	---------------------------	----------

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/17/03	DATE	April 17, 2003
----------	----------------------	------------	---------	------	----------------



Asphalt pavement materials around exterior of building.



Location of railroad bed adjacent to building.

P:\740881\Field Reports\HF49A\DFR 04-17-03

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Friday, April 18, 2003
CONTRACT		REPORT NO.	4/18/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50~55
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	0
F450	Crew Cab Rack Truck	1	Rich Stapleton	0
Power Washer/Steamer		1	Jim Goldrick	10
Air Compressor, 185 cfm		1	Dale Dolph	5
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Prepared for soil sampling at Bldg 307.
- Established soil sample locations outside of building. Existing conditions contain crushed limestone materials to facilitate building drainage.  
Collected 12 surface soil samples.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

--	--	--

Accidents reported today:	0	Accidents to date:	0
---------------------------	---	--------------------	---

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/18/03	DATE	April 18, 2003
----------	----------------------	------------	---------	------	----------------

No Photos Taken During Sampling Activities.

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Monday, April 21, 2003
CONTRACT		REPORT NO.	4/21/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50~55
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
Power Washer/Steamer		1	Jim Goldrick	10
Air Compressor, 185 cfm		1		
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Layout of rinsate sampling grids for the interior of buildings 301 and 307.
- Obtained characterization samples for the rinsate liquid generated during cleaning at 301 and 307.
- Obtained interior PCB wipe samples at building 307.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

--	--	--

Accidents reported today:	0	Accidents to date:	0
---------------------------	---	--------------------	---

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/21/03	DATE	April 21, 2003
----------	----------------------	------------	---------	------	----------------



Obtaining a PCB wipe sample.

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Tuesday, April 22, 2003
CONTRACT		REPORT NO.	4/22/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50~55
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
Power Washer/Steamer		1	Jim Goldrick	10
Air Compressor, 185 cfm		1	Dale Dolph	0
Generator, 5000 watt		1		
Vacuum Storage Tank 5000 gal		1		

MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Obtained interior wall wipe samples in Bldg 307.
- Began collecting rinsate samples from Bldg 307.
- Completed 10 random rinsate samples at 307.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

--	--	--

<b>Accidents reported today:</b>	<b>0</b>	<b>Accidents to date:</b>	<b>0</b>
----------------------------------	----------	---------------------------	----------



JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/22/03	DATE	April 22, 2003
----------	----------------------	------------	---------	------	----------------



Rinsate berm.



Collecting rinsate samples.

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Wednesday, April 23, 2003
CONTRACT		REPORT NO.	4/23/03
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50=55
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Dan Douglass	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
			Jim Goldrick	10

MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Completed rinsate samples at Bldg 307.
- Mobilized to Bldg 301 for rinsate and wipe samples.
- Obtained 8 rinsate samples inside Bldg 301.
- Secured sites for the evening.

**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

Dan Hoffner	PARSONS	QC
-------------	---------	----

Accidents reported today:	0	Accidents to date:	0
---------------------------	---	--------------------	---

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/23/03	DATE	April 23, 2003
----------	----------------------	------------	---------	------	----------------



Rinsate dike and collection pump.



Sampling Equipment

**Daily Field Report**

JOB NAME	Bldg 301/307 Closure Remedial Action	DATE	Thursday, April 24 2003
CONTRACT		REPORT NO.	4/2403
PROJECT		WEATHER	Sunny/Clear
JOB #	743157	TEMPERATURE	50~55
CLIENT	Corps Of Engineers	TIME/HRS	630 -5:00

Equipment	Model/Type	Quantity	Work Force/Trade	Quantity
F250	Crew Cab Pickup	1	Yvonne Walseman	10
F450	Crew Cab Rack Truck	1	Rich Stapleton	10
			Jim Goldrick	10

**MATERIALS DELIVERED TO, OR REMOVED FROM THE JOBSITE**

Material Removed/Delivered	Quantity	Source	Unit

**Work in progress or complete (including subcontractors):**

- Completed rinsate samples at Bldg 301 on the exterior ramp locations.
- Obtained PCB wipe samples from the interior floor and walls.
- Obtained chip samples of the exterior ramp areas for PCB analysis.
- Secured sites for the evening.
- Demobilized from the site.


**Verbal discussions/Instructions:**

**Visitors and Subcontractors:**

Dan Hoffner	PARSONS	QC
-------------	---------	----

Accidents reported today:	0	Accidents to date:	0
---------------------------	---	--------------------	---

JOB NAME	Bldg 301/307 Closure	REPORT NO.	4/24/03	DATE	April 24, 2003
----------	----------------------	------------	---------	------	----------------



Rinsate location on exterior ramp.



PCB Wipe sample Bldg 301.

P:\740881\Field Reports\HF49A\DFR 04-24-03