

November 16, 2009

Mr. John Nohrstedt
U.S. Army Corps of Engineers
Engineering and Support Center, Huntsville
Attn: CEHNC-FS-IS
4820 University Square
Huntsville, Alabama 35816-1822

SUBJECT: Draft RCRA Closure Report for the Mixed Waste Storage Facility, Building 803 (SEAD-72), Seneca Army Depot Activity, Romulus, New York, Contract W912DY-08-D-0003, Delivery Order 0003

Dear Mr. Nohrstedt:

Parsons Infrastructure & Technology Group Inc. (Parsons) is pleased to submit the Draft RCRA Closure Report for SEAD-72, the former Mixed Waste Storage Facility (Building 803) located at the Seneca Army Depot Activity in Romulus, New York. This work was performed in accordance with the Scope of Work for Delivery Order 0003 under Contract W912DY-08-D-0003.

Parsons appreciates the opportunity to provide you with the Closure Report for this work. Should you have any questions, please do not hesitate to call me at 617-449-1570 to discuss them.

Sincerely,



Jeffrey Adams
Project Manager

Enclosures

cc: S. Absolon, SEDA
K. Hodginott, USACHPPM
R. Walton, USAEC
R. Battaglia, USACE, NY
File



PARSONS

100 High Street • Boston, Massachusetts 02110 • (617) 552-5000 • www.parsons.com

November 16, 2009

Mr. Julio Vazquez
U.S. Environmental Protection Agency, Region II
Superfund Federal Facilities Section
290 Broadway, 18th Floor
New York, NY 10007-1866

Mr. Kuldeep K. Gupta, P.E.
New York State Department of Environmental Conservation (NYSDEC)
Division of Environmental Remediation
Remedial Bureau A, Section C
625 Broadway
Albany, NY 12233-7015

Mr. Mark Sergott
Bureau of Environmental Exposure Investigation, Room 300
New York State Department of Health
547 River Street, Flanigan Square
Troy, NY 12180

SUBJECT: Draft RCRA Closure Report for the Mixed Waste Storage Facility, Building 803 (SEAD-72), Seneca Army Depot Activity, Romulus, New York; EPA Site ID# NY0213820830 and NY Site ID# 8-50-006

Dear Mr. Vazquez/Mr. Gupta/Mr. Sergott:

Parsons Infrastructure & Technology Group Inc. (Parsons) is pleased to submit the Draft RCRA Closure Report for SEAD-72, the former Mixed Waste Storage Facility (Building 803) located at the Seneca Army Depot Activity in Romulus, New York (EPA Site ID# NY0213820830 and NY Site ID# 8-50-006).

Should you have any questions, please do not hesitate to call me at 617-449-1570 to discuss them.

Sincerely,



Jeffrey W. Adams
Project Manager

Enclosures

cc: M. Heaney, TechLaw
S. Absalom, SEDA
R. Walton, USAEC

J. Nohrstedt, USACE, Huntsville
K. Hoddinott, USACHPPM
R. Battaglia, USACE, NY






US Army, Engineering & Support Center
Huntsville, AL



Seneca Army Depot Activity
Romulus, NY



DRAFT

CLOSURE REPORT

THE FORMER MIXED WASTE STORAGE FACILITY, BUILDING 803 (SEAD-72)
SENECA ARMY DEPOT ACTIVITY

Contract No. W912DY-08-D-0003
Task Order No. 0003
EPA Site ID# NY0213820830
NY Site ID# 8-50-006

PARSONS

November 2009

**DRAFT
CLOSURE REPORT**

**FOR THE FORMER MIXED WASTE STORAGE FACILITY, BUILDING 803 (SEAD-72)
SENECA ARMY DEPOT ACTIVITY, ROMULUS, NEW YORK**

Prepared for:

**U.S. ARMY CORPS OF ENGINEERS, ENGINEERING AND SUPPORT CENTER
HUNTSVILLE, ALABAMA**

and

**SENECA ARMY DEPOT ACTIVITY
ROMULUS, NEW YORK**

Prepared by:

**PARSONS
100 High Street
Boston, MA 02110**

Contract Number W912DY-08-D-0003

Task Order No. 0003

EPA Site ID# NY0213820830

NY Site ID# 8-50-006

November 2009

TABLE OF CONTENTS

List of Tables	ii
List of Figures	ii
List of Appendices.....	ii
PROFESSIONAL ENGINEER CERTIFICATION	iii
1.0 INTRODUCTION	1-1
1.1 SUMMARY	1-1
1.2 SITE DESCRIPTION.....	1-3
1.3 CLOSURE PERFORMANCE STANDARD.....	1-4
1.4 CONCLUSIONS	1-4
2.0 CLOSURE ACTIVITIES	2-1
2.1 REMOVAL OF HAZARDOUS WASTE INVENTORY	2-1
2.2 DECONTAMINATION.....	2-1
2.3 CONFIRMATORY SAMPLING.....	2-1
2.3.1 Rinsate Samples	2-2
2.3.2 Building 803 Confirmation Samples	2-2
2.4 DISPOSAL.....	2-2
2.4.1 Dirt and Debris Waste	2-2
2.4.2 Decontamination Water.....	2-3
2.4.3 Personal Protective Equipment	2-3
2.5 DATA REPORTING AND ANALYSIS	2-3
2.5.1 Rinsate Samples	2-3
2.6 SURVEY PLAT	2-3
2.7 PROFESSIONAL ENGINEER REVIEW AND CERTIFICATION	2-4
2.8 SCHEDULE	2-4
3.0 CONCLUSIONS AND RECOMMENDATIONS	3-1
3.1 CONCLUSIONS.....	3-1
3.2 RECOMMENDATIONS	3-1

LIST OF TABLES

Table 1	Rinseate Samples Results
---------	--------------------------

LIST OF FIGURES

Figure 1	Building 803 Location Map
Figure 2	Building 803 Layout
Figure 3	Rinseate Sampling Locations

LIST OF APPENDICES

Appendix A	Analytical Results
Appendix B	Disposal Documentation
Appendix C	Daily Field Reports

PROFESSIONAL ENGINEER CERTIFICATION

To the best of my knowledge, after thorough investigation, I certify that the information contained in or accompanying this submission is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Thomas Andrews, P.E.
Parsons Infrastructure & Technology Group, Inc.
NYS Professional Engineer 047438

1.0 INTRODUCTION

This Closure Report presents the details of the work performed and the results achieved as part of the closure of SEAD-72, the former Mixed Waste Storage Facility (Building 803) at the Seneca Army Depot Activity (SEDA or the Depot) in Seneca County, New York. Historically, SEAD-72 (Building 803) was used for the storage of mixed chemical and radiological wastes that were generated at the Depot during its military mission, prior to their characterization, and final disposal at licensed, off-site disposal sites. Building 803 was originally listed as a greater than 90 day storage facility for mixed hazardous and radiological wastes in SEDA's Resource Conservation and Recovery Act Part B Permit application; however, the Army rescinded the permit application prior to its approval by, and the facility operated under interim status throughout its operational life.

Closure of Building 803 was performed by personnel of Parsons Infrastructure & Technology Group Inc. (Parsons) and St. George Enterprise, Inc. (St. George) working under contract to the U.S. Army, Engineering and Support Center, Huntsville (Army) on behalf of the Seneca Army Depot Activity. The SEDA is a listed New York Inactive Waste Site ID# 8-50-006 and as a National Priorities List (NPL) Site CERCLIS ID # NY0213820830.

The work performed at SEAD-72, Building 803 was completed in accordance with the Closure Plan entitled *Resource Conservation and Recovery Act (RCRA) Closure Plan, Former RCRA Unit Building 803-Mixed Waste Storage Facility, Solid Waste Management Unit (SWMU) – SEAD-72, Seneca Army Depot Activity in Romulus, New York* (Parsons, October 2005). The objective of the work was to obtain regulatory closure by meeting the objectives of Title 6 New York Code of Rules and Regulations (6 NYCRR) Subpart 373-3.7, Interim Status Standards for Owners and Operators of Hazardous Waste Facilities (NYSDEC, March 15, 2002). The Closure Plan for SEAD-72 was approved by the New York State Department of Environmental Conservation (NYSDEC) in a letter dated July 31, 2006. In accordance with agreements reached between representatives of the Army, the NYSDEC, and the U.S. Environmental Protection Agency Region II (EPA) closure of SEAD-72, Building 803 was delayed until such time as closure operations could be conducted in sequence with other remedial actions that were scheduled for SEAD-12, the Radiological Disposal Pit Site, within which SEAD-72 is located.

1.1 SUMMARY

Active use of SEAD-72 as a storage facility for mixed hazardous and radiological wastes ceased concurrent with the termination of Depot's military mission. This facility has been unoccupied and inactive since 1996, and has been a subject of Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) studies and investigations performed in SEAD-12 since approximately 1999. SEAD-72 (Building 803) is located within the land that is designated as SEAD-12, and was a facility in which similar hazardous substances and materials were handled during the active days of the military mission of SEAD-12.

SEAD-72 was surveyed for evidence of residual radiological contaminants during the radiological survey that was performed as part of the overall SEAD-12 Remedial Investigation (RI) between 1999

and 2003. As is reported in the *Radiological Survey Report – SEAD-12* (Parsons, 2003), the only area identified within Building 803 that posed a potential concern due to residual levels of radioactive contaminants was a shelf located within Room 6 of the building. Elevated levels of alpha and beta radiation were detected on this shelf during the Phase I building surveys; gamma measurements obtained for this shelf were within area background levels. Both dry and tritium smear samples collected from the shelf were within background levels, indicating that any contamination present on the shelf unit was not removable.

During subsequent Phase II building surveys, in-situ gamma spectroscopy analysis was performed on the shelf in an attempt to further identify the radionuclides that were present. However, the gamma component of the contamination was not of sufficient intensity or strength to allow for identification, and the gamma spectroscopy system was not able to differentiate between the contamination on the shelf and background levels found in the area of the shelf unit.

Based on the initial elevated alpha/beta measurements obtained, it was assumed that the residual detected radioactivity on the shelf was associated with radium paint. Subsequent to the completion of the radiological survey, the Army removed the contaminated shelf unit and disposed it as low level radioactive waste. Therefore, decontamination of Building 803 for radiological contaminants was not required or proposed as a component of the RCRA Closure of Building 803.

The land surrounding the exterior of Building 803 (SEAD-72) has also been evaluated as part of the SEAD-12 RI. The results of the SEAD-12 RI indicate that there are no chemical or radiological contaminants of concern identified at levels that posed potential risks or hazards to future receptors in environmental media surrounding the exterior of Building 803. The results of the RI are documented in the *Final Remediation Investigation Report* (Parsons 2002).

Closure of Building 803 was completed by surveying the interior of the former Mixed Waste Storage Facility (SEAD-72) for evidence of residual mixed or chemical waste inventories, followed by the removal and disposal of abandoned shelving units, and the cleaning of the building's interior surfaces to remove chemical contamination that may have remained within the building since its use was terminated. Once the interior surfaces were cleaned and decontaminated, aqueous rinsate samples were collected and analyzed for specific chemical contaminants known to have been accumulated in the facility during its operational life to confirm the efficacy of the decontamination process. The results obtained from the analysis of the rinsate samples were compared to Toxicity Characteristic regulatory limits for trichloroethene (0.5 milligrams per liter) defined in Title 6 NYCRR Part 371.3(e) (also Title 40 Code of Federal Regulations [CFR] Part 261.24).

Observations made at the time the decontamination work was performed at Building 803 indicated that there was no residual inventory of mixed or chemical hazardous waste present in the Mixed Waste Storage Facility (SEAD-72). Old metal shelving units were removed and sent as scrap to a metal recycler. Finally, the results of the confirmatory rinsate samples collected and characterized as part of the final closure operations indicate that there is no residual chemical contamination within the vacant building at levels in excess of approved clean up goals.

This remainder of this report documents and provides details of the closure activities conducted within Building 803. Included with the summary report are analytical results (**Appendix A**), disposal documentation (**Appendix B**), and Daily Field Reports (**Appendix C**).

1.2 SITE DESCRIPTION

Building 803 is located within the SEDA's former Weapons Storage Area (WSA) and is generally surrounded by activities that are located within SEAD-12, which is also known as the Radioactive Disposal Pit Sites. SEAD-72 is located in the northern portion of SEDA, approximately 3.5 miles northwest of the Depot's main entry gate off New York State Highway, Route 96 (**Figure 1**).

Building 803 was constructed in 1958. Building 803 meets requirements for conforming storage status for mixed waste storage facilities as defined in 6 NYCRR Part 373. This facility was designated as a RCRA unit in SEDA's Part 373 Permit Application and is a unit that remains regulated under RCRA interim status provisions (Facility Number NY0213820830).

Building 803 (SEAD-72) is built atop and into a mound of earth. The building consists of a fake above ground building, four subsurface interior vaults, two subsurface interior hallways, a covered and walled hallway leading into the building, and a loading platform. The above ground building measures approximately 55 by 42 feet in size and is composed entirely of concrete which is covered with exterior trim that include false windows and false doors. The subterranean portion of Building 803 measures approximately 35 by 25 feet in size and consists of four storage vaults situated exterior to a central underground entry hallway. The four storage vaults each measure approximately 10 feet by 13 feet in size and are separated from one another and the outside by concrete walls and ceilings that are 18 inches thick. The concrete floors of the subsurface structures are not sloped, but they originally contained floor drains in each of the vaults (**Figure 2**) that fed into a common discharge line. As is indicated in **Figure 2**, the liquid wastes captured in the drains originally appear to have exited the building via an outflow pipe that discharged at the west end of the loading platform. However, at some time prior to the performance of the SEAD-12 RI and building survey work in 1999, the drains were plugged with concrete. The paint used on both the interior and exterior walls of the Building 803 is known to contain lead.

During Building 803's operational use, mixed waste generated by the cleaning and maintenance of mission components in neighboring buildings were transported to the building for storage prior to shipment off-site for disposal. Mixed wastes were stored in new, removable head type, 55-gallon drums that conformed to appropriate DOT specifications for containers holding hazardous waste in transport. The mixed waste consisted of solvent-wetted paper wipes that were used to clean low-level radioactive components. Solvents used on the paper wipes included isopropanol, Freon® 11, trichloroethene, acetone, and toluene.

Once used, the wipes were segregated by solvent type, bagged, sealed with tape, double bagged, sealed with tape again, labeled for identification, and then placed in the drum until it was shipped off-site under manifest. At any one time, Building 803 could hold a maximum of 96, 55-gallon drums

(24 per vault) if the drums were double stacked in each vault. Building 803 was cleared of drummed hazardous and mixed waste in 1996 and has not been used as a waste storage facility since that time.

As part of the Army's military mission termination and Base Closure requirements, Building 803 was evaluated for the presence of residual radiological contamination between 1999 and 2003 using a combination of real-time alpha, beta, and gamma radiation detection equipment and the collection of smear and swipe samples for more detailed chemical evaluations. Wipe samples were also collected from the floor drains and vents of Building 803 and all resulting data was analyzed in accordance with the Multi Agency Radiation Survey and Site Investigation Manual (EPA 2002). The results of the scanning and wipe sample analysis indicated that Building 803 is compliant with the Derived Concentration Guideline Levels (DCGLs), which were based on NYSDEC Technical and Administrative Guidance Memorandum (TAGM) #4003 that allows for 10 milli-rem per year as an acceptable dose equivalent exposure.

1.3 CLOSURE PERFORMANCE STANDARD

The closure performance standard as written in 6 NYCRR Part 373-3.7(b) states that the facility must be closed in a manner that:

- Minimizes the need for further maintenance.
- Controls, minimizes or eliminates, to the extent necessary to protect human health and the environment, post closure escape of hazardous waste, hazardous constituents, leachate, contaminated run-off, or hazardous waste decomposition products to the ground or surface waters or to the atmosphere.

Subdivisions of 373 3.10(h), 3.11(f), 3.12(g), 3.13(g), 3.14(d), 3.15(e), 3.16(e), 3.17(e) and 3.30(c) are NOT applicable to this closure, as written in the standard.

1.4 CONCLUSIONS

The primary objective of the closure plan was to perform the work necessary to obtain clean closure of the building's interior in conformance with the closure performance standard. Review of the confirmatory rinsate analytical data indicates that the clean closure of Building 803 has been achieved. Therefore, it can be concluded that;

- No further maintenance is needed.
- The building poses no threat to human health or the environment.
- Because all hazardous materials have been removed and the building has been decontaminated, there is no chance for post closure escape of hazardous waste or hazardous constituents.
- Because the building is in good repair and is no longer used for storage of hazardous materials, there is no chance for future leachate, contained run-off or hazardous waste decomposition products migrating to the ground, surface waters or to the atmosphere.

2.0 CLOSURE ACTIVITIES

2.1 REMOVAL OF HAZARDOUS WASTE INVENTORY

All hazardous or mixed waste inventories were removed from Building 803 in 1996, prior to the start of final closure work. Upon accessing the building to perform closure operations, Parsons verified that there was no residual inventory of hazardous or mixed waste present within the building. Residual metal shelving units were found in the storage vaults and these were brushed and vacuumed clean prior to being removed and sent to a scrap metal dealer for recycle. Solid waste (e.g., accumulated dust, dirt, flaking paint, etc.) was generated and collected as part of the closure operations, but once these were characterized, they were determined to be non-hazardous and were disposed as solid wastes at licensed landfills. No hazardous or mixed wastes were generated or accumulated as a result of the closure activity.

2.2 DECONTAMINATION

The building was decontaminated manually to the fullest extent practical through the use of rigorous industrial cleaning methods. All interior floor, wall, and ceiling surfaces were initially manually abraded using stiff bristle brushes to capture removable peeling paint, dirt, and other debris. Accumulated paint, dirt, and debris were recovered using broom and dust pan and high efficiency particulate air (HEPA) vacuums. Approximately one-half of a 55-gallon open head drum of dirt, debris, and paint chips were collected using the brushes and HEPA-vacuum. One sample of the accumulated dirt, debris, and dust was collected and sent to an analytical laboratory for waste disposal determinations.

Once the removal of gross levels of debris was completed, interior floor, wall, and ceiling surfaces were decontaminated using a high-pressure water wash. During the high-pressure water wash cycles, the entry doorway to Building 803 was sealed to prevent the spread of wash and waste waters beyond the inside of the building and the containment area. Additionally, as was noted earlier in Section 1.2, the floor drains located in each of the vault cells and in the entry hallway are plugged and prevent release of water to the surrounding environment. All resulting wash and waste water from the high-pressure water wash process were recovered, placed into a single fifty-five gallon drum, allowed to settle, and then recoverable solid components of the collected waste stream were removed and added to the accumulated dry debris container.

2.3 CONFIRMATORY SAMPLING

Upon the completion of the decontamination process, rinsate samples were collected to confirm the degree of decontamination achieved. Confirmation sampling required at Building 803 was limited to the collection of aqueous samples in accordance with the State of New York's *Rinsate Sample Collection Protocol* for the characterization of residual levels of five solvents previously used on the paper wipes that were stored in the building.

2.3.1 Rinsate Samples

Rinsate samples were collected from areas that were generally flat and horizontal (i.e., floors and ramps) where damming techniques could be successfully implemented. Prior to collecting rinsate samples, grids were laid out on the floors of the buildings by placing chalk marks at the appropriate intervals, and sampling locations were chosen based on a random numbering selection process.

An Ultra Spill Berm® (temporary floor dike made of flexible, non absorbing polyurethane material) was used to contain rinsate water. The berm was molded into an approximately 400 square inch surface area (i.e., 20 inches by 20 inches). Sampling was initiated by pouring approximately 2 liters of laboratory grade distilled, deionized water into the bermed area and letting it stand in contact with the building's surface for a period of time not less than ten minutes.

The water was then recovered from the bermed area using a dedicated, disposable plastic pipette and bulb and transferred into the sample collection vials. Each of the collected samples was labeled and recorded (Sample ID, Location ID, and time) in the field logbook and on the chain of custody.

After each sample was collected, the berm was decontaminated usingalconox and water followed by a laboratory grade water rinse. The pipette assembly was disposed after each of the required samples was collected.

Rinsate samples were analyzed for isopropanol, Freon® 11 (trichlorofluoromethane), trichloroethylene, acetone, and toluene. The sample analyses were conducted by Columbia Analytical Services Inc , a laboratory certified by the NYSDOH, and were performed in accordance with "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods," EPA Publication SW-846 (Third Edition (November 1986), as amended by Updates: I (July 1992), II (September 1994), IIA (August 1993), IIB (January 1995), III (December 1996), and IIIA (April 1998), and later approved revisions), hereinafter referred to as "SW-846".

2.3.2 Building 803 Confirmation Samples

Seven (7) locations were chosen for collection of rinsate samples, plus one additional quality assurance and quality control (QA/QC) sample. The samples were collected from the surfaces (i.e., ramps and contained floor) of Building 803 and the locations are shown on **Figure 3**. The analytical results for the conformational samples are presented in **Table 1**. A review of this table indicates that the results of the rinsate sample are all below the defined limit, and thus the decontamination of Building 803, SEAD-72 is considered complete.

2.4 DISPOSAL

2.4.1 Dirt and Debris Waste

All dirt and debris recovered from the interior cleaning of Building 803 were contained in approximately one-half of a 55-gallon open head drum. A sample of this material was collected and sent to the analytical laboratory for the characterization of TCLP metals. The results of this determination are shown in Appendix B. All reported results for metals were below TCLP

permissible levels. Based on this determination, dirt and debris recovered from the cleaning of SEAD-72 (Building 803) was disposed at Seneca Meadows Landfill as non-hazardous waste.

2.4.2 Decontamination Water

Wastewater generated from the power washing of Building 803 was collected and pumped into a single 55-gallon DOT approved drum. All pumps, hoses, containers and equipment used during the decontamination operations were decontaminated after use by triple flushing/rinsing all exposed or wetted surfaces with clean, potable water. The rinse waters were added to the drummed decontamination waste liquid drums. Approximately one full drum of wastewater was generated during the decontamination of Building 803.

The residual liquid waste water (approximately 50 to 55 gallons) collected from SEAD-72 was subsequently transferred into the Bakers tank that was brought to the SEAD-12 removal action work site to store surface water that was captured in the disposal pit excavations. Approximately 17,000 gallons of waste water was accumulated from the excavations at SEAD-12 and the decontamination of SEAD-72.

A sample of the water from the Bakers tank was collected and characterized prior to disposal. The results of the chemical analysis for the water in the Bakers tank are provided in Appendix B. Based on the receipt and review of the analytical results for the water in the Bakers tank, the Seneca County Sewer Authority authorized the Army to dispose of the waste water from the SEAD-12 excavations and the SEAD-72 decontamination process in their sewage collection system, upstream of their treatment plant.

2.4.3 Personal Protective Equipment

Disposable personnel protective equipment worn by workers was collected and placed in a dumpster for disposal as a non-hazardous waste at the Ontario County Landfill.

2.5 DATA REPORTING AND ANALYSIS

2.5.1 Rinsate Samples

Analytical results from the rinsate samples are summarized on **Table 1** and the laboratory data sheets are provided in **Appendix A**. The analytical results were compared to the 500 microgram per liter (ug/L) Toxicity Characteristic (TC) level for trichloroethene described in 6 NYCRR 373.3(e) (also 40 CRF Part 261.24). This cleanup value was also used as the comparator value for isopropanol, Freon® 11, acetone, and toluene since there are no TC levels for these compounds. Concentrations of the five compounds detected in all rinsate samples were significantly below the TC cleanup value of 500 ug/L.

2.6 SURVEY PLAT

A survey plat is not required because there is no indication that any hazardous or mixed hazardous waste remains at SEAD-72, the former Mixed Waste Storage Facility at the Seneca Army Depot.

2.7 PROFESSIONAL ENGINEER REVIEW AND CERTIFICATION

As per 6 NYCRR Part 373-3.7(f), this report shall serve as certification of the closures of Building 803. Tom Andrews, P.E. has reviewed this report and certifies that the work was done in accordance with the approved closure plan and 6 NYCRR Part 373-3.7. See Certification of Closure at the beginning of this report.

2.8 SCHEDULE

Building decontamination was performed between July 20 and 21, 2009.

Post decontamination confirmatory sampling was conducted on July 21, 2009.

3.0 CONCLUSIONS AND RECOMMENDATIONS

3.1 CONCLUSIONS

The decontamination effort performed on the interior of Building 803 removed all visible contamination. It can be concluded that clean closure has been achieved for Building 803 based on the results of confirmatory rinsate samples (see **Table 1**).

3.2 RECOMMENDATIONS

No further decontamination efforts are required based on the confirmatory sampling results.

Close SEAD-72 with regulatory concurrence.

TABLES

Table 1 Rinseate Samples Results

Table 1
SEAD-72 Rinseate Samples Results
Building 803 RCRA Closure Report
Seneca Army Depot Activity


SITE LOCATION	SEAD-72		SEAD-72		SEAD-72		SEAD-72		SEAD-72		SEAD-72		SEAD-72	
LOCATION ID	Grid-E26		Grid-L11		Grid-P14		Grid-VA12		Grid-VB3		Grid-VC18		Grid-VD25	
MATRIX	RINSEATE		RINSEATE		RINSEATE		RINSEATE		RINSEATE		RINSEATE		RINSEATE	
SAMPLE ID	S72-G-E26		S72-G-L11		S72-G-P14		S72-G-VA12		S72-G-VB3		S72-G-VC18		S72-G-VD25-D	
SAMPLE DATE	7/22/2009		7/22/2009		7/22/2009		7/22/2009		7/22/2009		7/22/2009		7/22/2009	
QC CODE	SA		SA		SA		SA		SA		SA		DU	
STUDY ID	SEAD-12 RA		SEAD-12 RA		SEAD-12 RA		SEAD-12 RA		SEAD-12 RA		SEAD-12 RA		SEAD-12 RA	
Parameter	Units	Maximum Value	Frequency of Detection	Cleanup Goal Value ¹	Number of Exceedances	Number of Times Detected	Number of Samples Analyzed	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)	Value (Q)
2-Propanol	UG/L	0	0%	500	0	0	8	100 U	100 U	100 U	100 U	100 U	100 U	100 U
Acetone	UG/L	5.3	75%	500	0	6	8	2.7 J	1.9 J	5.3 J	3.1 J	20 U	20 U	4.4 J
Toluene	UG/L	0	0%	500	0	0	8	5 U	5 U	5 U	5 U	5 U	5 U	5 U
Trichloroethene	UG/L	0	0%	500	0	0	8	5 U	5 U	5 U	5 U	5 U	5 U	5 U
Trichlorofluoromethane	UG/L	0	0%	500	0	0	8	5 U	5 U	5 U	5 U	5 U	5 U	5 U

Notes:
1. The cleanup goal (CUG) values were based on the 0.5 mg/L Toxicity Characteristic (TC) for trichloroethylene described in 40 CRF Part 261.24, and was applied to all five parameters.

FIGURES

- Figure 1 Building 803 Location Map
- Figure 2 Building 803 Layout
- Figure 3 Rinseate Sampling Locations


SEAD-12
Radiological Waste Burial Pit Sites
within Former Weapons Storage Area



BUILDING 803



SEAD-72



PARSONS

SENECA ARMY DEPOT ACTIVITY
BLDG 803
RCRA CLOSURE REPORT

FIGURE 1
BUILDING 803
LOCATION MAP

1" = 150'

NOVEMBER 2009



LEGEND

— Wall

- - - Drain line

D - floor drain

Notes: Floor drains were plugged with concrete as reported during a NYSDEC and NYSDOH site inspection in 1993.



PARSONS

SENECA ARMY DEPOT ACTIVITY
BLDG 803
RCRA CLOSURE REPORT

**FIGURE 2
BUILDING 803 LAYOUT**

1" = 8'

NOVEMBER 2009

Approximate Extent of Fake
Above Ground Structure

Exterior Loading Dock and Subterranean
Entrance to Storage Vault

LOADING
PLATFORM

D1
EXTERIOR HALLWAY
803-7

HALLWAY
803-1

VAULT No. 1
803-5

VAULT No. 2
803-6

VAULT No. 2
803-2

VAULT No. 4
803-3

HALLWAY
803-4

Approximate Extent of Inner
Subterranean Structure

← Approximately 25 feet →

← Approximately 42 feet →

↑ Approximately 35 feet ↓

↑ Approximately 55 feet ↓



LEGEND




Wall



Rinsate sample grid
P - Loading Platform
E - Exterior Hallway
L - Large Interior Hallway
V - Vault (A, B, C, or D)



Rinsate sample location



PARSONS

SENECA ARMY DEPOT ACTIVITY
BLDG 803
RCRA CLOSURE REPORT

FIGURE 3
BUILDING 803 -
RINSATE SAMPLING LOCATIONS

SCALE: 1" = 8'

NOVEMBER 2009

APPENDICES

- Appendix A Analytical Results
- Appendix B Disposal Documentation
- Appendix C Daily Field Reports

APPENDIX A
ANALYTICAL RESULTS



1 Mustard Street, Suite 250
Rochester, NY 14609

Date: August 03, 2009

Number of pages: _____

To:

Brendan Baranek-Olmstead
Parsons Engineering Science
100 High St. 4th Floor
Boston, MA 02110

Phone: 617-449-1570

Fax: 617-946-9777

From:

Michael Perry

Phone: 585-288-5380

Fax: 585-288-8475

RUSH REPORT

Submission #: R0904107

Project Reference: SEAD-72 803 Closure PROJECT #746762-02500

IMPORTANT NOTICE:

The documents accompanying this transmission may contain information which is legally privileged and/or confidential. The information is intended only for the use of the individual or entity named above. If you are not the intended recipient, or the person responsible for delivering it to the intended recipient, you are hereby notified that any disclosure, copying, distributing, or use of any information contained in this transmission is strictly PROHIBITED. If you have received this transmission in error, please immediately notify us by telephone and mail the original transmission to us. Thank you for your cooperation and assistance.

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-VA12
Lab Code: R0904107-001

Service Request: R0904107
Date Collected: 7/22/09 1500
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Analysis	
								Lot	Lot
Isopropanol	ND	U	100	13	1	NA	7/29/09 14:41		163312
Acetone	3.1	J	20	1.6	1	NA	7/29/09 14:41		163312
Toluene	ND	U	5.0	0.42	1	NA	7/29/09 14:41		163312
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 14:41		163312
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 14:41		163312

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	98	85-122	7/29/09 14:41		
Dibromofluoromethane	101	89-119	7/29/09 14:41		
Toluene-d8	96	87-121	7/29/09 14:41		

Comments: _____

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-VB3
Lab Code: R0904107-002

Service Request: R0904107
Date Collected: 7/22/09 1505
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis	
									Lot	Note
Isopropanol	ND	U	100	13	1	NA	7/29/09 15:13		163312	
Acetone	ND	U	20	1.6	1	NA	7/29/09 15:13		163312	
Toluene	0.47	J	5.0	0.42	1	NA	7/29/09 15:13		163312	
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 15:13		163312	
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 15:13		163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	98	85-122	7/29/09 15:13		
Dibromofluoromethane	99	89-119	7/29/09 15:13		
Toluene-d8	101	87-121	7/29/09 15:13		

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-VC18
Lab Code: R0904107-003

Service Request: R0904107
Date Collected: 7/22/09 1510
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Analysis		
								Lot	Lot	Note
Isopropanol	ND	U	100	13	1	NA	7/29/09 15:45		163312	
Acetone	ND	U	20	1.6	1	NA	7/29/09 15:45		163312	
Toluene	ND	U	5.0	0.42	1	NA	7/29/09 15:45		163312	
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 15:45		163312	
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 15:45		163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	98	85-122	7/29/09 15:45		
Dibromofluoromethane	97	89-119	7/29/09 15:45		
Toluene-d8	101	87-121	7/29/09 15:45		

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-VD25
Lab Code: R0904107-004

Service Request: R0904107
Date Collected: 7/22/09 1525
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Isopropanol	ND U	100	13	1	NA	7/29/09 16:17		163312	
Acetone	3.2 J	20	1.6	1	NA	7/29/09 16:17		163312	
Toluene	ND U	5.0	0.42	1	NA	7/29/09 16:17		163312	
Trichloroethene (TCE)	ND U	5.0	0.63	1	NA	7/29/09 16:17		163312	
Trichlorofluoromethane (CFC 11)	ND U	5.0	0.48	1	NA	7/29/09 16:17		163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	98	85-122	7/29/09 16:17		
Dibromofluoromethane	100	89-119	7/29/09 16:17		
Toluene-d8	95	87-121	7/29/09 16:17		

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
 Project: SEAD-72 803 Closure/746762-02500
 Sample Matrix: Water
 Sample Name: S72-G-L11
 Lab Code: R0904107-005

Service Request: R0904107
 Date Collected: 7/22/09 1530
 Date Received: 7/23/09
 Units: µg/L
 Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Analysis	
								Lot	Lot
Isopropanol	ND	U	100	13	1	NA	7/29/09 16:49	163312	
Acetone	1.9	J	20	1.6	1	NA	7/29/09 16:49	163312	
Toluene	0.42	J	5.0	0.42	1	NA	7/29/09 16:49	163312	
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 16:49	163312	
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 16:49	163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	98	85-122	7/29/09 16:49		
Dibromofluoromethane	99	89-119	7/29/09 16:49		
Toluene-d8	102	87-121	7/29/09 16:49		

Comments: _____

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-E26
Lab Code: R0904107-006

Service Request: R0904107
Date Collected: 7/22/09 1535
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Analysis	
								Lot	Lot Note
Isopropanol	ND	U	100	13	1	NA	7/29/09 17:21	163312	
Acetone	2.7	J	20	1.6	1	NA	7/29/09 17:21	163312	
Toluene	ND	U	5.0	0.42	1	NA	7/29/09 17:21	163312	
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 17:21	163312	
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 17:21	163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	97	85-122	7/29/09 17:21		
Dibromofluoromethane	100	89-119	7/29/09 17:21		
Toluene-d8	102	87-121	7/29/09 17:21		

Comments: _____

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-P14
Lab Code: R0904107-007

Service Request: R0904107
Date Collected: 7/22/09 1540
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Isopropanol	ND	U	100	13	1	NA	7/29/09 17:53		163312	
Acetone	5.3	J	20	1.6	1	NA	7/29/09 17:53		163312	
Toluene	ND	U	5.0	0.42	1	NA	7/29/09 17:53		163312	
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 17:53		163312	
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 17:53		163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	98	85-122	7/29/09 17:53		
Dibromofluoromethane	99	89-119	7/29/09 17:53		
Toluene-d8	95	87-121	7/29/09 17:53		

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-VD25-D
Lab Code: R0904107-008

Service Request: R0904107
Date Collected: 7/22/09 1525
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Isopropanol	ND	U	100	13	1	NA	7/29/09 18:24		163312	
Acetone	4.4	J	20	1.6	1	NA	7/29/09 18:24		163312	
Toluene	ND	U	5.0	0.42	1	NA	7/29/09 18:24		163312	
Trichloroethene (TCE)	ND	U	5.0	0.63	1	NA	7/29/09 18:24		163312	
Trichlorofluoromethane (CFC 11)	ND	U	5.0	0.48	1	NA	7/29/09 18:24		163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	96	85-122	7/29/09 18:24		
Dibromofluoromethane	98	89-119	7/29/09 18:24		
Toluene-d8	91	87-121	7/29/09 18:24		

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-72 803 Closure/746762-02500
Sample Matrix: Water
Sample Name: S72-G-BLK
Lab Code: R0904107-009

Service Request: R0904107
Date Collected: 7/22/09 1700
Date Received: 7/23/09

Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Isopropanol	ND U	100	13	1	NA	7/29/09 14:09		163312	
Acetone	ND U	20	1.6	1	NA	7/29/09 14:09		163312	
Toluene	0.52 J	5.0	0.42	1	NA	7/29/09 14:09		163312	
Trichloroethene (TCE)	ND U	5.0	0.63	1	NA	7/29/09 14:09		163312	
Trichlorofluoromethane (CFC 11)	ND U	5.0	0.48	1	NA	7/29/09 14:09		163312	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	99	85-122	7/29/09 14:09		
Dibromofluoromethane	102	89-119	7/29/09 14:09		
Toluene-d8	103	87-121	7/29/09 14:09		

Comments:

APPENDIX B
DISPOSAL DOCUMENTATION

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-12 RA/746762-02000
Sample Matrix: Water
Sample Name: WW1006-01
Lab Code: R0905678-005

Service Request: R0905678
Date Collected: 10/ 6/09 0900
Date Received: 10/ 6/09
Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Analysis	
								Lot	Lot Note
1,1,1-Trichloroethane (TCA)	1.0	U	1.0	0.45	1	NA	10/9/09 13:35	174059	
1,1,2,2-Tetrachloroethane	1.0	U	1.0	0.44	1	NA	10/9/09 13:35	174059	
1,1,2-Trichloroethane	1.0	U	1.0	0.45	1	NA	10/9/09 13:35	174059	
1,1,2-Trichloro-1,2,2-trifluoroethane	1.0	U	1.0	0.48	1	NA	10/9/09 13:35	174059	
1,1-Dichloroethane (1,1-DCA)	1.0	U	1.0	0.64	1	NA	10/9/09 13:35	174059	
1,1-Dichloroethene (1,1-DCE)	1.0	U	1.0	0.59	1	NA	10/9/09 13:35	174059	
1,2,4-Trichlorobenzene	1.0	U	1.0	0.46	1	NA	10/9/09 13:35	174059	
1,2-Dibromo-3-chloropropane (DBCP)	2.0	U	2.0	0.61	1	NA	10/9/09 13:35	174059	
1,2-Dibromoethane	1.0	U	1.0	0.43	1	NA	10/9/09 13:35	174059	
1,2-Dichlorobenzene	1.0	U	1.0	0.40	1	NA	10/9/09 13:35	174059	
1,2-Dichloroethane	1.0	U	1.0	0.42	1	NA	10/9/09 13:35	174059	
1,2-Dichloropropane	1.0	U	1.0	0.36	1	NA	10/9/09 13:35	174059	
1,3-Dichlorobenzene	1.0	U	1.0	0.84	1	NA	10/9/09 13:35	174059	
1,4-Dichlorobenzene	1.0	U	1.0	0.44	1	NA	10/9/09 13:35	174059	
2-Butanone (MEK)	5.0	U	5.0	1.0	1	NA	10/9/09 13:35	174059	
2-Hexanone	5.0	U	5.0	0.78	1	NA	10/9/09 13:35	174059	
4-Methyl-2-pentanone	5.0	U	5.0	0.71	1	NA	10/9/09 13:35	174059	
Acetone	2.9	J	10	1.6	1	NA	10/9/09 13:35	174059	
Benzene	1.0	U	1.0	0.42	1	NA	10/9/09 13:35	174059	
Bromodichloromethane	1.0	U	1.0	0.84	1	NA	10/9/09 13:35	174059	
Bromoform	1.0	U	1.0	0.32	1	NA	10/9/09 13:35	174059	
Bromomethane	2.0	U	2.0	0.58	1	NA	10/9/09 13:35	174059	
Carbon Disulfide	1.0	U	1.0	0.52	1	NA	10/9/09 13:35	174059	
Carbon Tetrachloride	1.0	U	1.0	0.36	1	NA	10/9/09 13:35	174059	
Chlorobenzene	1.0	U	1.0	0.44	1	NA	10/9/09 13:35	174059	
Chloroethane	2.0	U	2.0	0.36	1	NA	10/9/09 13:35	174059	
Chloroform	1.0	U	1.0	0.18	1	NA	10/9/09 13:35	174059	
Chloromethane	2.0	U	2.0	0.96	1	NA	10/9/09 13:35	174059	
Cyclohexane	2.0	U	2.0	0.66	1	NA	10/9/09 13:35	174059	
Dibromochloromethane	1.0	U	1.0	0.43	1	NA	10/9/09 13:35	174059	
Dichlorodifluoromethane (CFC 12)	1.0	U	1.0	0.53	1	NA	10/9/09 13:35	174059	
Dichloromethane	1.0	U	1.0	0.50	1	NA	10/9/09 13:35	174059	

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-12 RA/746762-02000
Sample Matrix: Water
Sample Name: WW1006-01
Lab Code: R0905678-005

Service Request: R0905678
Date Collected: 10/ 6/09 0900
Date Received: 10/ 6/09
Units: µg/L
Basis: NA

Volatile Organic Compounds by GC/MS

Analytical Method: 8260B

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Ethylbenzene	1.0	U	1.0	0.43	1	NA	10/9/09 13:35		174059	
Isopropylbenzene (Cumene)	1.0	U	1.0	0.36	1	NA	10/9/09 13:35		174059	
Methyl Acetate	10	U	10	0.62	1	NA	10/9/09 13:35		174059	
Methyl tert-Butyl Ether	1.0	U	1.0	0.45	1	NA	10/9/09 13:35		174059	
Methylcyclohexane	1.0	U	1.0	0.54	1	NA	10/9/09 13:35		174059	
Styrene	1.0	U	1.0	0.37	1	NA	10/9/09 13:35		174059	
Tetrachloroethene (PCE)	1.0	U	1.0	0.43	1	NA	10/9/09 13:35		174059	
Toluene	1.0	U	1.0	0.42	1	NA	10/9/09 13:35		174059	
Trichloroethene (TCE)	1.0	U	1.0	0.63	1	NA	10/9/09 13:35		174059	
Trichlorofluoromethane (CFC 11)	1.0	U	1.0	0.48	1	NA	10/9/09 13:35		174059	
Vinyl Chloride	1.0	U	1.0	0.52	1	NA	10/9/09 13:35		174059	
cis-1,2-Dichloroethene	1.0	U	1.0	0.48	1	NA	10/9/09 13:35		174059	
cis-1,3-Dichloropropene	1.0	U	1.0	0.38	1	NA	10/9/09 13:35		174059	
m,p-Xylenes	2.0	U	2.0	0.85	1	NA	10/9/09 13:35		174059	
o-Xylene	1.0	U	1.0	0.56	1	NA	10/9/09 13:35		174059	
trans-1,2-Dichloroethene	1.0	U	1.0	0.45	1	NA	10/9/09 13:35		174059	
trans-1,3-Dichloropropene	1.0	U	1.0	0.25	1	NA	10/9/09 13:35		174059	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
4-Bromofluorobenzene	101	85-122	10/9/09 13:35		
Dibromofluoromethane	104	89-119	10/9/09 13:35		
Toluene-d8	104	87-121	10/9/09 13:35		

Comments: _____

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-12 RA/746762-02000
Sample Matrix: Water
Sample Name: WW1006-01
Lab Code: R0905678-005

Service Request: R0905678
Date Collected: 10/ 6/09 0900
Date Received: 10/ 6/09
Units: µg/L
Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270C
Prep Method: EPA 3510C

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Analysis		Note
								Lot	Lot	
1,2,4-Trichlorobenzene	10	U	10	0.92	1	10/ 7/09	10/10/09 01:31	97751	174300	
1,2-Dichlorobenzene	10	U	10	1.2	1	10/ 7/09	10/10/09 01:31	97751	174300	
1,3-Dichlorobenzene	10	U	10	0.73	1	10/ 7/09	10/10/09 01:31	97751	174300	
1,4-Dichlorobenzene	10	U	10	0.60	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,4,5-Trichlorophenol	10	U	10	0.74	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,4,6-Trichlorophenol	10	U	10	1.1	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,4-Dichlorophenol	10	U	10	0.91	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,4-Dimethylphenol	10	U	10	0.59	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,4-Dinitrophenol	50	U	50	44	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,4-Dinitrotoluene	10	U	10	1.3	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,6-Dinitrotoluene	10	U	10	1.1	1	10/ 7/09	10/10/09 01:31	97751	174300	
2-Chloronaphthalene	10	U	10	0.55	1	10/ 7/09	10/10/09 01:31	97751	174300	
2-Chlorophenol	10	U	10	0.77	1	10/ 7/09	10/10/09 01:31	97751	174300	
2-Methylnaphthalene	10	U	10	0.66	1	10/ 7/09	10/10/09 01:31	97751	174300	
2-Methylphenol	10	U	10	0.99	1	10/ 7/09	10/10/09 01:31	97751	174300	
2-Nitroaniline	50	U	50	21	1	10/ 7/09	10/10/09 01:31	97751	174300	
2-Nitrophenol	10	U	10	0.87	1	10/ 7/09	10/10/09 01:31	97751	174300	
3,3'-Dichlorobenzidine	10	U	10	1.3	1	10/ 7/09	10/10/09 01:31	97751	174300	
3- and 4-Methylphenol Coelution	10	U	10	1.5	1	10/ 7/09	10/10/09 01:31	97751	174300	
3-Nitroaniline	50	U	50	14	1	10/ 7/09	10/10/09 01:31	97751	174300	
4,6-Dinitro-2-methylphenol	50	U	50	24	1	10/ 7/09	10/10/09 01:31	97751	174300	
4-Bromophenyl Phenyl Ether	10	U	10	1.1	1	10/ 7/09	10/10/09 01:31	97751	174300	
4-Chloro-3-methylphenol	10	U	10	0.86	1	10/ 7/09	10/10/09 01:31	97751	174300	
4-Chloroaniline	10	U	10	0.92	1	10/ 7/09	10/10/09 01:31	97751	174300	
4-Chlorophenyl Phenyl Ether	10	U	10	0.77	1	10/ 7/09	10/10/09 01:31	97751	174300	
4-Nitroaniline	50	U	50	18	1	10/ 7/09	10/10/09 01:31	97751	174300	
4-Nitrophenol	50	U	50	12	1	10/ 7/09	10/10/09 01:31	97751	174300	
Acenaphthene	10	U	10	0.84	1	10/ 7/09	10/10/09 01:31	97751	174300	
Acenaphthylene	10	U	10	0.73	1	10/ 7/09	10/10/09 01:31	97751	174300	
Anthracene	10	U	10	0.64	1	10/ 7/09	10/10/09 01:31	97751	174300	
Benz(a)anthracene	10	U	10	0.78	1	10/ 7/09	10/10/09 01:31	97751	174300	
Benzo(a)pyrene	10	U	10	0.63	1	10/ 7/09	10/10/09 01:31	97751	174300	

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
 Project: SEAD-12 RA/746762-02000
 Sample Matrix: Water
 Sample Name: WW1006-01
 Lab Code: R0905678-005

Service Request: R0905678
 Date Collected: 10/ 6/09 0900
 Date Received: 10/ 6/09
 Units: µg/L
 Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270C
 Prep Method: EPA 3510C

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Benzo(b)fluoranthene	10	U	10	0.62	1	10/ 7/09	10/10/09 01:31	97751	174300	
Benzo(g,h,i)perylene	10	U	10	0.83	1	10/ 7/09	10/10/09 01:31	97751	174300	
Benzo(k)fluoranthene	10	U	10	0.96	1	10/ 7/09	10/10/09 01:31	97751	174300	
Benzyl Alcohol	10	U	10	0.74	1	10/ 7/09	10/10/09 01:31	97751	174300	
2,2'-Oxybis(1-chloropropane)	10	U	10	1.1	1	10/ 7/09	10/10/09 01:31	97751	174300	
Bis(2-chloroethoxy)methane	10	U	10	1.3	1	10/ 7/09	10/10/09 01:31	97751	174300	
Bis(2-chloroethyl) Ether	10	U	10	1.2	1	10/ 7/09	10/10/09 01:31	97751	174300	
Bis(2-ethylhexyl) Phthalate	10	U	10	1.2	1	10/ 7/09	10/10/09 01:31	97751	174300	
Butyl Benzyl Phthalate	10	U	10	0.90	1	10/ 7/09	10/10/09 01:31	97751	174300	
Carbazole	10	U	10	0.78	1	10/ 7/09	10/10/09 01:31	97751	174300	
Chrysene	10	U	10	1.1	1	10/ 7/09	10/10/09 01:31	97751	174300	
Di-n-butyl Phthalate	10	U	10	0.99	1	10/ 7/09	10/10/09 01:31	97751	174300	
Di-n-octyl Phthalate	10	U	10	0.89	1	10/ 7/09	10/10/09 01:31	97751	174300	
Dibenz(a,h)anthracene	10	U	10	0.77	1	10/ 7/09	10/10/09 01:31	97751	174300	
Dibenzofuran	10	U	10	0.71	1	10/ 7/09	10/10/09 01:31	97751	174300	
Diethyl Phthalate	10	U	10	0.90	1	10/ 7/09	10/10/09 01:31	97751	174300	
Dimethyl Phthalate	10	U	10	0.74	1	10/ 7/09	10/10/09 01:31	97751	174300	
Fluoranthene	10	U	10	0.72	1	10/ 7/09	10/10/09 01:31	97751	174300	
Fluorene	10	U	10	0.76	1	10/ 7/09	10/10/09 01:31	97751	174300	
Hexachlorobenzene	10	U	10	0.96	1	10/ 7/09	10/10/09 01:31	97751	174300	
Hexachlorobutadiene	10	U	10	0.67	1	10/ 7/09	10/10/09 01:31	97751	174300	
Hexachlorocyclopentadiene	10	U	10	0.70	1	10/ 7/09	10/10/09 01:31	97751	174300	
Hexachloroethane	10	U	10	0.71	1	10/ 7/09	10/10/09 01:31	97751	174300	
Indeno(1,2,3-cd)pyrene	10	U	10	0.65	1	10/ 7/09	10/10/09 01:31	97751	174300	
Isophorone	10	U	10	0.96	1	10/ 7/09	10/10/09 01:31	97751	174300	
N-Nitrosodi-n-propylamine	10	U	10	1.1	1	10/ 7/09	10/10/09 01:31	97751	174300	
N-Nitrosodimethylamine	10	U	10	0.64	1	10/ 7/09	10/10/09 01:31	97751	174300	
N-Nitrosodiphenylamine	10	U	10	0.72	1	10/ 7/09	10/10/09 01:31	97751	174300	
Naphthalene	10	U	10	0.60	1	10/ 7/09	10/10/09 01:31	97751	174300	
Nitrobenzene	10	U	10	0.90	1	10/ 7/09	10/10/09 01:31	97751	174300	
Pentachlorophenol (PCP)	50	U	50	31	1	10/ 7/09	10/10/09 01:31	97751	174300	
Phenanthrene	10	U	10	0.75	1	10/ 7/09	10/10/09 01:31	97751	174300	

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-12 RA/746762-02000
Sample Matrix: Water
Sample Name: WW1006-01
Lab Code: R0905678-005

Service Request: R0905678
Date Collected: 10/ 6/09 0900
Date Received: 10/ 6/09
Units: µg/L
Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270C
Prep Method: EPA 3510C

Analyte Name	Result	Q	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
Phenol	10	U	10	0.54	1	10/ 7/09	10/10/09 01:31	97751	174300	
Pyrene	10	U	10	0.84	1	10/ 7/09	10/10/09 01:31	97751	174300	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q	Note
2,4,6-Tribromophenol	89	46-134	10/10/09 01:31		
2-Fluorobiphenyl	75	46-110	10/10/09 01:31		
2-Fluorophenol	47	12-84	10/10/09 01:31		
Nitrobenzene-d5	77	44-117	10/10/09 01:31		
Phenol-d6	35	10-70	10/10/09 01:31		
p-Terphenyl-d14	88	40-133	10/10/09 01:31		

Comments: _____

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-12 RA/746762-02000
Sample Matrix: Water
Sample Name: WW1006-01
Lab Code: R0905678-005

Service Request: R0905678
Date Collected: 10/ 6/09 0900
Date Received: 10/ 6/09

Basis: NA

Inorganic Parameters

Analyte Name	Method	Result Q	Units	MRL	MDL	Dilution Factor	Date Extracted	Date Analyzed
Aluminum, Total	6010B	660	µg/L	100	20	1	10/ 8/09	10/12/09 09:42
Antimony, Total	6010B	60 U	µg/L	60	4	1	10/ 8/09	10/12/09 09:42
Arsenic, Total	6010B	10 U	µg/L	10	4	1	10/ 8/09	10/12/09 09:42
Barium, Total	6010B	147	µg/L	20	8	1	10/ 8/09	10/12/09 09:42
Beryllium, Total	6010B	5.0 U	µg/L	5.0	0.2	1	10/ 8/09	10/12/09 09:42
Cadmium, Total	6010B	5.0 U	µg/L	5.0	0.2	1	10/ 8/09	10/12/09 09:42
Calcium, Total	6010B	45600	µg/L	1000	200	1	10/ 8/09	10/12/09 09:42
Chromium, Total	6010B	10 U	µg/L	10	2	1	10/ 8/09	10/12/09 09:42
Cobalt, Total	6010B	50 U	µg/L	50	2	1	10/ 8/09	10/12/09 09:42
Copper, Total	6010B	3 J	µg/L	20	3	1	10/ 8/09	10/12/09 09:42
Iron, Total	6010B	1510	µg/L	100	40	1	10/ 8/09	10/12/09 09:42
Lead, Total	6010B	50 U	µg/L	50	1	1	10/ 8/09	10/12/09 09:42
Magnesium, Total	6010B	16600	µg/L	1000	100	1	10/ 8/09	10/12/09 09:42
Manganese, Total	6010B	225	µg/L	10	1	1	10/ 8/09	10/12/09 09:42
Mercury, Total	7470A	0.30 U	µg/L	0.30	0.02	1	10/ 7/09	10/7/09 15:01
Nickel, Total	6010B	6 J	µg/L	40	3	1	10/ 8/09	10/12/09 09:42
Potassium, Total	6010B	2300	µg/L	2000	100	1	10/ 8/09	10/13/09 12:42
Selenium, Total	6010B	10 U	µg/L	10	5	1	10/ 8/09	10/12/09 09:42
Silver, Total	6010B	10 U	µg/L	10	3	1	10/ 8/09	10/12/09 09:42
Sodium, Total	6010B	11800	µg/L	1000	100	1	10/ 8/09	10/13/09 12:42
Thallium, Total	6010B	10 U	µg/L	10	3	1	10/ 8/09	10/12/09 09:42
Vanadium, Total	6010B	50 U	µg/L	50	5	1	10/ 8/09	10/12/09 09:42
Zinc, Total	6010B	5 J	µg/L	20	3	1	10/ 8/09	10/12/09 09:42

Comments:

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Parsons Engineering Science
Project: SEAD-12/746762-02000
Sample Matrix: Soil

Service Request: R0904596
Date Collected: 8/13/09 1230
Date Received: 8/14/09
Pre-Prep Date: 8/17/09

Sample Name: S12DB01
Lab Code: R0904596-001

Basis: NA

**Toxicity Characteristics Leachate Procedure (TCLP)
 Inorganic Parameters**

Pre-Prep Method: EPA 1311

Analyte Name	Method	Result Q	Units	MRL	Dilution Factor	Date Extracted	Date Analyzed
Arsenic	6010B	ND U	mg/L	0.50	1	8/20/09	8/24/09 19:57
Barium	6010B	ND U	mg/L	1.0	1	8/20/09	8/24/09 19:57
Cadmium	6010B	ND U	mg/L	0.10	1	8/20/09	8/24/09 19:57
Chromium	6010B	0.21	mg/L	0.10	1	8/20/09	8/24/09 19:57
Lead	6010B	ND U	mg/L	0.10	1	8/20/09	8/24/09 19:57
Mercury	7470A	ND U	mg/L	0.00030	1	8/25/09	8/25/09 15:20
Selenium	6010B	ND U	mg/L	0.50	1	8/20/09	8/24/09 19:57
Silver	6010B	ND U	mg/L	0.10	1	8/20/09	8/24/09 19:57

Comments:

APPENDIX C
DAILY FIELD REPORTS

Daily Report

Date: 7/20/2008 **Day:** Monday **Weather Conditions:**
Job # 746762 Hot 70's

Site Name: SEAD 72 Bldg 803 **Project:** Seneca Army Depot

Parsons:		St George	
TC Andrews	11	Supt	1
Ben Mcallister		Operators	
		Laborers	2
Visitors	Representing	Teamster	

Equipment

Fan
 Job Truck
 Power wash
 power vacuum
 lights
 generator

Health and Safety: **PPE Level(s):** C

Tool Box meeting Discussed lead exposure and clean up requirements

Work Performed:

Access, ventilate and inspect facility. Identified metals shelving units. No residual wastes identified.
 Brush walls, floors, ceiling to removed coarse debris and dirt. Remove shelving units and transport for scrap.
 Capture coarse debris place in 55 gallon drum
 HEPA- vac all surfaces, add dust, debris to 55 gallon drum
 Seal door to prevent water escape
 Powerwash all surfaces, capture waste and drum

Disposal	Loads	Total to date	Estimated tons	To. Tons to date	Sampling:
			0	0	
			0	0	
				0	

Deliveries Material	Loads	CY	Tons

Prepared by: _____
 Thomas C Andrews

Daily Report

Date: 7/21/2008 **Day:** Wednesday **Weather Conditions:**
Job # 746762 cloudy 80's

Site Name: SEAD 72 Bldg 803 **Project:** Seneca Army Depot

Parsons: St George
 TC Andrews Supt
 Ben Mcallister Operators
 Laborers
Visitors **Representing** Teamster

Equipment
 Fan
 Job Truck
 Power wash
 power vacuum
 lights
 generator
Health and Safety: **PPE Level(s):** C
 Tool Box meeting Discussed lead exposure and clean up requirements

Work Performed:
 Sampled the test areas. Per work plan. Rinsate samples for VOCs
 Prepared coc for sample transport
 Ship samples to lab
 Demob all equipment pending return of results.

Disposal	Loads	Total to date	Estimated tons	To. Tons to date	Sampling:
			0	0	
			0	0	
			0	0	

Deliveries Material	Loads	CY	Tons

Prepared by: _____
 Thomas C Andrews